

## 5-Port Solenoid Valve



Series VQC

# **Connector Type Manifold**

# Series VQC1000/2000/4000

## **Outstanding response times** and long life

(Metal seal: Single type with light and surge suppressor)

VQC1100: 10ms ±2ms: 200 million cycles VQC2100: 20ms ±2ms; 200 million cycles VQC4100: 17ms ±3ms; 100 million cycles


## Compact and high flow

| -        |            | F              |      | Applicable |                             |          |      |           |
|----------|------------|----------------|------|------------|-----------------------------|----------|------|-----------|
| Type     | Manifold   | Metal seal     |      |            | Rubber                      | cylinder |      |           |
| (Series) | pitch (mm) | C[dm³/(s·bar)] | b    | Cv         | C[dm <sup>3</sup> /(s·bar)] | b        | Cv   | size (mm) |
| VQC1000  | 10.5       | 0.72           |      | 0.18       | 1.0                         | 0.30     | 0.25 | to ø50    |
| VQC2000  | 16         | 2.6            | 0.15 | 0.60       | 3.2                         | 0.30     | 0.80 | to ø80    |
| VQC4000  | 25         | 6.9            | 0.17 | 1.7        | 7.3                         | 0.38     | 2.0  | to ø140   |

**Connector entry direction** can be changed with a single push (F, P kit)

Note) Values for 2-position single from 4 to 5 and from 2 to 3. (From A to R1 and from B to R2).

The connector entry direction can be changed from the top



Input blocks


Accommodates gateway type serial wiring

- Because just one gateway unit controls up to 4 branch lines, it offers much more freedom in choosing valve mounting locations in comparison to other serial units.
- A single cable from the gateway provides both signal and power to each branch, thus eliminating the need for separate power connections for each manifold valve and input block.
- The use of a multi-connector for input blocks makes manifold station expansion or reduction a breeze.




EX250

# A wide variety of prepackaged wiring configurations



- · Our six standard wiring packages bring a world of ease to wiring and maintenance work, while the protective enclosures of four of them conform to IP67 standards.
- The S Kit is compatible with a combined I/O unit. (If used with Gateway unit, SI must be output only.)

## Conforming to IP67 for protection from dust (Based on IEC529) and moisture (For kits S, T, L and M)



(Refer to the connector wiring diagram)

Printed circuit board patterns between connectors are shifted at every station. This allows for viable connections to take place without necessarily specifying whether the manifold station is double, single, or mixed wiring.

# Dual 3-port valves, 4 positions VQC1000/2000 (Rubber seal type only)


- Two 3-port valves built into one body.
- The 3-port valves on the A and B sides can operate independently.
- When used as 3-port valves, only half the number of stations is required.
- Can also be used as a 4-position, 5-port type valve.

Exhaust center: VQC1A01

VQC2A01

Pressure center: VQC1B01

**VQC2B01** 



| Model              | A side        | B side        | JIS symbol   |
|--------------------|---------------|---------------|--|
| VQC1A01<br>VQC2A01 | N.C.<br>valve | N.C.<br>valve | (A) (B)<br>(B)<br>(B)<br>(R1) 1 (R2)                                   |
| VQC1B01<br>VQC2B01 | N.O.<br>valve | N.O.<br>valve | (Å) (B)  ZEV 1 (K1) (R2)  (R1) (R2)                                    |
| VQC1C01<br>VQC2C01 | N.C.<br>valve | N.O.<br>valve | (A) (B)<br>(B)<br>(B)<br>(B)<br>(B)<br>(B)<br>(C)<br>(C)<br>(C)<br>(C) |


# **Base-Mounted type: Variations**

|         |             |               |                            | nic                                       |  |   | S   | Kit  |                                     |  |
|---------|-------------|---------------|----------------------------|---|--|---|---|--|-------------------------------------|--|
|         |             |               | C[dm <sup>3</sup> /        | ctance<br>(s·bar)]                        |  |   |   | nsmission                                      |                                     |  |
| A       | .1          | 1110          | ∥\ ar                      | es of<br>o EXH<br>4 to 5<br>nd<br>2 to 3) | ore size   | Gateway application Compatible network Remote I/O DeviceNet PROFIBUS-DP CC-Link | Compatible network  DeviceNet  PROFIBUS-DP  CC-Link  AS-i | Compatible network  • DeviceNet  • PROFIBUS-DP | Compatible network • CC-Link Output |  |
|         |             | Single/Double | 3-position (Closed center) | Applicable bore size                      | Decentralized Serial Wiring Gateway application requires a gateway unit and communication cable separately. Contact SMC for more details.  Serial unit: EX500 Conforms to IP67 | • CANopen I/O  Serial unit: EX250 Conforms to IP67                              | Serial unit: EX240 Conforms to IP65                       | Serial unit: EX126 Conforms to IP67            |                                     |  |
| Series  | Metal seal  | VQC1□00       | 0.72                       | 0.72                                      | to ø50   |   |   |  | 0                                   |  |
| VQC1000 | Rubber seal | VQC1□01       | 1.0                        | 0.65                                      | 10 200   |   |   |  |                                     |  |
| Series  | Metal seal  | VQC2□00       | 2.6                        | 2.0                                       | 40.700   |   |   |  |                                     |  |
| VQC2000 | Rubber seal | VQC2□01       | 3.2                        | 2.2                                       | to ø80   |   |   |  |                                     |  |
| Series  | Metal seal  | VQC4□00       | 6.9                        | 6.3                                       | to =4.40   |   |   |  |                                     |  |
| VQC4000 | Rubber seal | VQC4□01       | 7.3                        | 6.4                                       | to ø140  |   |   |  |                                     |  |

| F Kit   | P Kit  | <b>T</b> Kit   | L Kit   | M Kit  | Port   | size   |
|---|--|--|---|--|--|--|
| D-sub connector  Compatible with D-sub connector that complies with MIL standard. | Flat ribbon cable  Flat ribbon cable  Compatible with flat ribbon cable connector that complies with MIL standard. | Terminal block box  Terminal block box  (Terminal blocks)  Terminals are concentrated in compact clusters within the terminal block box.  Conforms to IP67 | Lead wire  IP67 enclosure with use of multiple wire cable with sheath and waterproof connector  25-core cable  Conforms to IP67 | Multiple connector  Multiple connector  IP67 enclosure with use of waterproof multiple connector  26-pin  Conforms to IP67 | SUP<br>EXH port<br>1, 3<br>(P, R)  | Cylinder<br>port<br>2, 4<br>(A, B)   |
|   | 0  | 0  | 0   | 0  | C8 (for ø8)<br>N9 (ø5/16")   | C3 (for ø3.2)<br>C4 (for ø4)<br>C6 (for ø6)<br>M5 (M5 thread)<br>N1 (ø1/8")<br>N3 (ø5/32")<br>N7 (ø1/4")   |
|   | 0  | 0  | 0   | 0  | C10 (for ø10)  N11 (ø3/8")  In case of branch type C12 (for ø12) N13 (ø1/2")             | C4 (for ø4)<br>C6 (for ø6)<br>C8 (for ø8)<br>N3 (ø5/32")<br>N7 (ø1/4")<br>N9 (ø5/16")  |
| 0   |  | 0  | 0   |  | <sup. port=""> Rc 1/2 (NPT, NPTF, G)  <exh. port=""> Rc 3/4 (NPT, NPTF, G)</exh.></sup.> | C8 (for Ø8)<br>C10 (for Ø10)<br>C12 (for Ø12)<br>N7 (Ø1/4")<br>N9 (Ø5/16")<br>N11 (Ø3/8")<br>Rc 1/4<br>Rc 3/8<br>Rc 1/4<br>(bottom ported)<br>(NPT, NPTF, G) |

## Cylinder average speed

This chart is provided as guidelines only. For performance under various conditions, use SMC's Model Selection Program before making a judgment.





- Values at extension of a directly coupled cylinder when meter-out speed controllers are used with the needle full open.
   The average speed of the cylinder is obtained by dividing the stroke by the total stroke time.
- \* The load ratio is obtained by the following formula: ((Load weight x 9.8)/ Theoretical output) x 100%

## **Conditions**

| Base    | Series CJ2       | Series CM2                  | Series MB, CA | Series CS1 |          |
|---------|------------------|-----------------------------|---------------|------------|----------|
|         | Tube x Length    | 1                           | ı             | _          |          |
| VQC1000 | Speed controller | Α                           | S3001F-0      | 6          | _        |
|         | Silencer         | P                           | _             |            |          |
|         | Tube x Length    | T0604 x 1m T0806 x 1m       |               |            |          |
| VQC2000 | Speed controller | AS3001F-06                  | AS300         | _          |          |
|         | Silencer         | Α                           | _             |            |          |
|         | Tube x Length    | T0604 x 1m                  | T1075 x 1m    | T1209      | 9 x 1m   |
| VQC4000 | Speed controller | AS3001F-06 AS4001F-10 AS400 |               | )1F-12     |          |
|         | Silencer         |                             | AN400-04      |            | AN400-04 |

## Conditions (With SGP (stainless steel gas piping))

| Direc   | ct piping        | Series MB, CA Series CS1 |  |  |  |
|---------|------------------|--------------------------|--|--|--|
|         | Tube x Length    | SGP10A x 1m              |  |  |  |
| VQC4000 | Speed controller | AS420-03                 |  |  |  |
|         | Silencer         | AN400-04                 |  |  |  |
|         |                  |                          |  |  |  |



## Series VQC1000

# **Base-Mounted Type**


# **Plug-in Unit**

 $\epsilon$ 



Refer to the SMC website for detailed information on models suitable for overseas use.

## **How to Order Manifolds**



SI unit COM

|   | ۰۰۰۰  | :+ COM |           | EX250       |         |      |         | EX500     |             |         |            | EX126   |
|---|-------|--------|-----------|-------------|---------|------|---------|-----------|-------------|---------|------------|---------|
|   | oi un | it COM | DeviceNet | PROFIBUS-DP | CC-Link | AS-i | CANopen | DeviceNet | PROFIBUS-DP | CC-Link | Remote I/O | CC-Link |
|   | Nil   | +COM   | _         | _           | 0       | _    | _       | 0         | 0           | 0       | 0          | 0       |
|   | N     | -COM   | 0         | 0           | _       | 0    | 0       | 0         | 0           | 0       | 0          | _       |
| _ |       | •      | •         |             |         |      |         | •         |             |         | •          |         |




Note) Leave the box blank for the SI unit COM without SI unit (SD0).


### Number of input blocks (Fill out for I/O unit only)

| Nil                  | Without SI unit/input block |  |  |  |  |  |  |
|----------------------|-----------------------------|--|--|--|--|--|--|
| 0                    | Without input block         |  |  |  |  |  |  |
| 1 With 1 input block |                             |  |  |  |  |  |  |
|                      |                             |  |  |  |  |  |  |
| 8                    | 8 With 8 input blocks       |  |  |  |  |  |  |




#### **How to Order Valves**





## **Manifold Options**


Blanking plate assembly VVQ1000-10A-1




SUP block plate VVQ1000-16A




Perfect block VVQ1000-FPG-□□




Dual flow fitting assembly VVQ1000-52A-C8



Blanking plate with connector VVQ1000-1C□-□




Individual SUP spacer VVQ1000-P-1-C6




EXH block plate assembly VVQC1000-19A-8-64




Elbow fitting assembly VVQ1000-F-L□



Port plug VVQ0000-58A




Electrical wiring specifications [-K]




0


Individual EXH spacer VVQ1000-R-1-C6




DIN rail mounting bracket [-D] VVQ1000-57A for {F,L,M,P,S (EX500) kit} VVQC1000-57A-S for {S (EX250) kit} VVQC1000-57A-T for {T,S (EX126) kit}



Silencer (for EXH port) AN200-KM8 AN203-KM8



Back pressure check valve assembly [-B] VVQ1000-18A




Standard manifolds are for double wiring, but mixed wiring (single and double wiring) can be specified as options.

SOL. B<sub>O</sub> 19

COM o 13


Connector terminal no



Direct EXH outlet with built-in silencer [-S]



Blanking plug KQ2P-□





## Series VQC2000

# Base-Mounted Type


# **Plug-in Unit**

 $C \in$ 



Refer to the SMC website for detailed information on models suitable for overseas use.

#### **How to Order Manifolds**







With 8 input blocks

8

### **How to Order Valves**




#### Kit designation/Electrical entry/Cable length




## **Manifold Options**


Blanking plate assembly VVQ2000-10A-1




SUP block plate VVQ2000-16A




Perfect block




Dual flow fitting assembly VVQ2000-52A-C10




Individual SUP spacer VVQ2000-P-1-C8




Elbow fitting assembly VVQ2000-F-L□




Port plug VVQ1000-58A



Individual EXH spacer VVQ2000-R-1-C8




EXH block plate VVQ2000-19A



Electrical wiring specifications [-K]

0






DIN rail mounting bracket [-D] VVQC2000-57A for {F,L,M,P,S (EX500) kit}

VVQC2000-57A-S for {S (EX250) kit} VVQC2000-57A-T

Silencer (for EXH port) AN200-KM10



Back pressure check valve assembly [-B] VVQ2000-18A




Name plate [-N] VVQ2000-N-Stations (1 to max. no. of stations)




Standard manifolds are for double wiring, but mixed wiring (single and double wiring) can be specified as options.

Connector terminal no.

Direct EXH outlet with built-in silencer [-S]



Blanking plug KQ2P-□





## Series VQC4000

# **Base-Mounted Type**


# Plug-in Unit


 $\epsilon$ 




Refer to the SMC website for detailed information on models suitable for overseas use.


### **How to Order Manifolds**





#### **How to Order Valves**





Note) For a 20P flat ribbon cable, the cable assembly must be ordered separately

Flat ribbon cable kit (26P) with 1.5m cable

Flat ribbon cable kit (26P) with 3.0m cable

Flat ribbon cable kit (26P) with 5.0m cable

Flat ribbon cable kit (20P) without cable Note

PD0 Flat ribbon cable kit (26P) without cable

PD1

PD2

PD3

**PDC** 

Conforms to IP67

1 to 12 stations

(16 stations)

LD0

LD1

Lead wire kit 0.6m lead wire

Lead wire kit 1.5m lead wire

LD2 Lead wire kit 3.0m lead wire


Conforms to IP40

(16 stations)


(16 stations)

## **Manifold Options**


Blanking plate assembly VVQ4000-10A-1




Individual SUP spacer VVQ4000-P-1-03




Individual EXH spacer VVQ4000-R-1-02




SUP./EXH. block plate VVQ4000-16A




Throttle valve spacer VVQ4000-20A-1




Residual pressure release valve perfect spacer VVQ4000-25A-1 Note 1)



SUP stop valve spacer VVQ4000-37A-1



Interface regulator ARBQ4000-00-8-1





Note1) Perfect spacers with residual pressure release valve cannot be combined with external pilot specifications.



### **Models**



2-position single




2-position double (metal)



2-position double (rubber)



3-position closed centre




3-position exhaust centre



3-position pressure centre



3-position exhaust centre with pressure release valves




4-position dual 3-port valve (A)



4-position dual 3-port valve (B)



4-position dual 3-port valve (C)



| (0      |                       |                      |             |         |                             | Flov | / char | acteristics                 |      |        | Response   | Note 2)<br>e time ms |        |
|---------|-----------------------|----------------------|-------------|---------|-----------------------------|------|--------|-----------------------------|------|--------|------------|----------------------|--------|
| Series  |                       | No. of               | Mode        | el      | 1→4, 2 (                    | P→A, | B)     | 4, 2→5, 3 (A,               | B→R  | 1, R2) | Standard:  | Low                  | Weight |
| S       | S                     | olenoids             |             |         | C[dm <sup>3</sup> /(s•bar)] | b    | Cv     | C[dm <sup>3</sup> /(s•bar)] | b    | Cv     | 1W         | wattage              | g      |
|         | چ                     | Cingle               | Metal seal  | VQC1100 | 0.70                        | 0.15 | 0.16   | 0.72                        | 0.25 | 0.18   | 12 or less | 15 or less           | 64     |
|         | sitio                 | Single               | Rubber seal | VQC1101 | 0.85                        | 0.20 | 0.21   | 1.0                         | 0.30 | 0.25   | 15 or less | 20 or less           | 04     |
|         | 2-position            | Double               | Metal seal  | VQC1200 | 0.70                        | 0.15 | 0.16   | 0.72                        | 0.25 | 0.18   | 10 or less | 13 or less           |        |
|         |                       | Double               | Rubber seal | VQC1201 | 0.85                        | 0.20 | 0.21   | 1.0                         | 0.30 | 0.25   | 15 or less | 20 or less           | ]      |
| 0       |                       | Closed               | Metal seal  | VQC1300 | 0.68                        | 0.15 | 0.16   | 0.72                        | 0.25 | 0.18   | 20 or less | 26 or less           |        |
| 100     |                       | centre               | Rubber seal | VQC1301 | 0.70                        | 0.20 | 0.16   | 0.65                        | 0.42 | 0.18   | 25 or less | 33 or less           | ]      |
| VQC1000 | ition                 | Exhaust              | Metal seal  | VQC1400 | 0.68                        | 0.15 | 0.16   | 0.72                        | 0.25 | 0.18   | 20 or less | 26 or less           | 70     |
| >       | 3-position            | centre               | Rubber seal | VQC1401 | 0.70                        | 0.20 | 0.16   | 1.0                         | 0.30 | 0.25   | 25 or less | 33 or less           | 78     |
|         | မ                     | Pressure             | Metal seal  | VQC1500 | 0.70                        | 0.15 | 0.16   | 0.72                        | 0.25 | 0.18   | 20 or less | 26 or less           |        |
|         |                       | centre               | Rubber seal | VQC1501 | 0.85                        | 0.20 | 0.21   | 0.65                        | 0.42 | 0.18   | 25 or less | 33 or less           |        |
|         | 4-position            | Dual<br>3-port valve | Rubber seal | VQC1e01 | 0.70                        | 0.20 | 0.16   | 0.70                        | 0.20 | 0.16   | 25 or less | 33 or less           |        |
|         | _                     | Single               | Metal seal  | VQC2100 | 2.0                         | 0.15 | 0.46   | 2.6                         | 0.15 | 0.60   | 22 or less | 29 or less           | 90     |
|         | sitio                 | Siligle              | Rubber seal | VQC2101 | 2.2                         | 0.28 | 0.55   | 3.2                         | 0.30 | 0.80   | 24 or less | 31 or less           | 30     |
|         | 3-position 2-position | Double               | Metal seal  | VQC2200 | 2.0                         | 0.15 | 0.46   | 2.6                         | 0.15 | 0.60   | 15 or less | 20 or less           |        |
|         |                       | Double               | Rubber seal | VQC2201 | 2.2                         | 0.28 | 0.55   | 3.2                         | 0.30 | 0.80   | 20 or less | 26 or less           |        |
| 0       |                       | Closed               | Metal seal  | VQC2300 | 2.0                         | 0.15 | 0.46   | 2.0                         | 0.18 | 0.46   | 29 or less | 38 or less           |        |
| VQC2000 |                       | centre               | Rubber seal | VQC2301 | 2.0                         | 0.28 | 0.49   | 2.2                         | 0.31 | 0.60   | 34 or less | 44 or less           |        |
| စ္င     |                       | Exhaust              | Metal seal  | VQC2400 | 2.0                         | 0.15 | 0.46   | 2.6                         | 0.15 | 0.60   | 29 or less | 38 or less           | 110    |
| _       |                       | centre               | Rubber seal | VQC2401 | 2.0                         | 0.28 | 0.49   | 3.2                         | 0.30 | 0.80   | 34 or less | 44 or less           | "      |
|         | ြိ                    | Pressure             | Metal seal  | VQC2500 | 2.4                         | 0.17 | 0.57   | 2.0                         | 0.18 | 0.46   | 29 or less | 38 or less           |        |
|         |                       | centre               | Rubber seal | VQC2501 | 3.2                         | 0.28 | 0.80   | 2.2                         | 0.31 | 0.60   | 34 or less | 44 or less           |        |
|         | 4-position            | Dual<br>3-port valve | Rubber seal | VQC2B01 | 1.8                         | 0.28 | 0.46   | 1.8                         | 0.28 | 0.46   | 34 or less | 44 or less           |        |
|         |                       | Single               | Metal seal  | VQC4100 | 6.2                         | 0.19 | 1.5    | 6.9                         | 0.17 | 1.7    | 20 or less | 22 or less           | 230    |
|         | 2-position            | Single               | Rubber seal | VQC4101 | 7.2                         | 0.43 | 2.1    | 7.3                         | 0.38 | 2.0    | 25 or less | 27 or less           | 200    |
|         | -pod-                 | Double               | Metal seal  | VQC4200 | 6.2                         | 0.19 | 1.5    | 6.9                         | 0.17 | 1.7    | 12 or less | 12 or less           | 260    |
|         | 2                     | Double               | Rubber seal | VQC4201 | 7.2                         | 0.43 | 2.1    | 7.3                         | 0.38 | 2.0    | 15 or less | 15 or less           | 200    |
| 0       |                       | Closed               | Metal seal  | VQC4300 | 5.9                         | 0.23 | 1.5    | 6.3                         | 0.18 | 1.6    | 45 or less | 47 or less           |        |
| VQC4000 |                       | centre               | Rubber seal | VQC4301 | 7.0                         | 0.34 | 1.9    | 6.4                         | 0.42 | 1.9    | 50 or less | 52 or less           |        |
| စ္      | _                     | Exhaust              | Metal seal  | VQC4400 | 6.2                         | 0.18 | 1.5    | 6.9                         | 0.17 | 1.7    | 45 or less | 47 or less           | 280    |
| >       | 3-position            | centre               | Rubber seal | VQC4401 | 7.0                         | 0.38 | 1.9    | 7.3                         | 0.38 | 2.0    | 50 or less | 52 or less           | 200    |
|         | od-                   | Pressure             | Metal seal  | VQC4500 | 6.2                         | 0.18 | 1.9    | 6.4                         | 0.18 | 1.6    | 45 or less | 47 or less           |        |
|         | 3                     | centre               | Rubber seal | VQC4501 | 7.0                         | 0.38 | 1.9    | 7.1                         | 0.38 | 2.0    | 50 or less | 52 or less           |        |
|         |                       | Perfect              | Metal seal  | VQC4600 | 2.7                         | _    | _      | 3.7                         | _    | _      | 55 or less | 57 or less           | 500    |
|         |                       | renect               | Rubber seal | VQC4601 | 2.8                         | _    | _      | 3.9                         | _    | _      | 62 or less | 64 or less           | 300    |



Note 1) Values represented in this column are in the following conditions: VQC1000: Cylinder port size C6 without a back pressure check valve VQC2000: Cylinder port size C8 without a back pressure check valve VQC4000: Cylinder port size Rc 3/8

Note 2) Values represented in this column are based on JISB8375-1981 (operating with clean air and a supply pressure of 0.5MPa. Equipped with light and surge voltage suppressor. Values vary depending on the pressure as well as the air quality.) Values for double types are when the switch is ON.

## **Standard Specifications**

|                           | Va           | lve Configuration       | n                | Metal seal   | Rubber seal                   |  |  |  |
|---------------------------|--------------|-------------------------|------------------|--|-------------------------------|--|--|--|
|                           | Flo          | uid                     |                  | Air/Inc  | ert gas                       |  |  |  |
|                           | 8            | Max. operating          | pressure         | 0.7MPa (High pressure type: 1.0MPa) Note 4)  |                               |  |  |  |
|                           | /20          |                         | Single           | 0.1MPa   | 0.15MPa                       |  |  |  |
|                           | 8            | Min. operating          | Double           | 0.1  | MPa                           |  |  |  |
|                           | VQC1000/2000 | pressure                | 3-position       | 0.1MPa   | 0.2MPa                        |  |  |  |
| ions                      | >            |                         | 4-position       | _  | 0.15MPa                       |  |  |  |
| icat                      | 0            | Max. operating p        | ressure Note 3   | 1.0MPa   | (0.7MPa)                      |  |  |  |
| ecif                      | 400          | Min. operating pressure | Single           | 0.15MPa  | 0.2MPa                        |  |  |  |
| Valve specifications      | ဥ            |                         | Double           | 0.15MPa  |                               |  |  |  |
| Valv                      | >            |                         | 3-position       | 0.15MPa  | 0.2MPa                        |  |  |  |
|                           | Pr           | oof pressure            |                  | 1.5  | MPa                           |  |  |  |
|                           | An           | nbient and fluid t      | emperature       | -10 to 50°C Note 1)  |                               |  |  |  |
|                           | Lu           | ıbrication              |                  | Not required   |                               |  |  |  |
|                           | Ma           | anual override          |                  | Push type/Locking type (tool required)/Locking type (manual override) Note 5)/Slide locking type Note 5) |                               |  |  |  |
|                           | lm           | pact resistance/Vibra   | ation resistance | 150/30 m/s <sup>2 Note 2)</sup>  |                               |  |  |  |
|                           | En           | nclosure                |                  | Dust proof (co   | Dust proof (conforms to IP67) |  |  |  |
| S                         | Ra           | ated coil voltage       |                  | 24\  | VDC                           |  |  |  |
| tion                      | Al           | lowable voltage         | fluctuation      | ±10% of rated voltage  |                               |  |  |  |
| Electrical specifications | Co           | oil insulation typ      | е                | Equivalent to B type   |                               |  |  |  |
| Ele<br>peci               |              | ower consumption        | on 24VDC         | 1W DC (42mA), 0.5W DC (21mA)   |                               |  |  |  |
| S                         | (C           | urrent)                 | 12VD0            | 1W DC (83mA),  | 0.5W DC (42mA)                |  |  |  |

Note 1) Use dry air to prevent condensation at low temperatures.



Note 2) **Impact resistance:** No malfunction resulted from the impact test using a drop impact tester. The test was performed one time each in the axial and right angle directions of the main valve and armature, for both energized and de-energized states. Vibration resistance: No malfunction occurred in a one-sweep test between 45 and 2000Hz. Test was performed in the axial and right angle directions of the main valve and armature for both energized and de-energized states.

Note 3) Values in ( ) are for the low wattage (0.5W) specification.

Note 4) Metal seal type only.
Note 5) Only for VQC1000/2000.

## **Manifold Specifications**

|         |             |  | ı         | Piping specifica   | tions  | Note 2)  | Applicable             | 5-station  |
|---------|-------------|--|-----------|--|--|--|------------------------|--|
| Series  | Base model  | Connection type  | Port      | Port si  | ze Note 1)   | Applicable stations  | solenoid               | weight   |
|         |             |  | direction | 1, 3 (P, R)  | 2, 4 (A, B)  | Stations   | valves                 | (g)  |
| VQC1000 | VV5QC11-□□□ | ■ F Kit: D-sub connector ■ P Kit: Flat cable ■ T Kit: Terminal block box ■ S Kit: Serial transmission ■ L Kit: Lead wire ■ M Kit: Multiple connector | Side      | C8 (for Ø8)  Options Direct outlet with built-in silencer                            | C3 (for ø3.2)<br>C4 (for ø4)<br>C6 (for ø6)<br>M5 (M5 threads) | (F,L,M and P Kits<br>1 to 12 stations<br>T Kit<br>1 to 10 stations   | VQC1□00-5<br>VQC1□01-5 | 628<br>(Single)<br>759<br>(Double, 3P)                         |
| VQC2000 | VV5QC21-□□□ |  | Side      | C10 (for ø10) Options Direct outlet with built-in silencer Branch type C12 (for ø12) | C4 (for ø4)<br>C6 (for ø6)<br>C8 (for ø8)                      | S Kit 1 to 8 stations: EX500 1 to 12 stations: EX250 1 to 8 stations: EX250 EX126  | VQC2□00-5<br>VQC2□01-5 | 1051<br>(Single)<br>1144<br>(Double, 3P)                       |
| VQC4000 | VV5QC41-□□□ |  | Side      | P: Rc 1/2<br>R: Rc 3/4   | C8 (for Ø8) C10 (for Ø10) C12 (for Ø12) Rc 1/4 Rc 3/8          | F,L,M and P Kits (1 to 12 stations)  T Kit (1 to 10 stations)  S Kit (1 to 12 stations: EX2240, EX250)  1 to 8 stations: EX500  1 to 8 stations: EX126 | VQC4□00-5<br>VQC4□01-5 | 4150 • S Kit (without unit) • Solenoid weight is not included. |

Note 1) One-touch fittings in inch sizes are also available.

Note 2) An optional specification for special wiring is available to increase the maximum number of stations.



# S VQC1000/2000/4000 Kit (Serial Transmission Kit) Decentralized Serial wiring

## Gateway type serial transmission system

• Since wiring is "prepackaged" into one multi-connector type cable, wiring work is not only made easier, but much more accurate.

S Kit can be used by connecting to gateway unit.

## Gateway (GW) Unit Conforms to IP65



#### **How to Order**

EX500-G DN1

## Communication protocol


| DN1  | DeviceNet   | AB1-X1 | Remote I/O (RIO) |
|------|-------------|--------|------------------|
| PR1A | PROFIBUS-DP | MJ1    | CC-Link          |

#### **Specifications**

| Model  | EX500-GAB1-X1                   | EX500-GDN1   | EX500-GPR1A  | EX500-GMJ1                            |  |  |  |  |  |
|--|---------------------------------|--|--|---------------------------------------|--|--|--|--|--|
| Applicable PLC/<br>Communication<br>protocol | Rockwell<br>Automation<br>PLC   | DeviceNet<br>Release 2.0                                     | PROFIBUS-DP<br>(EN50170)   | CC-Link<br>Ver. 1.10                  |  |  |  |  |  |
| Communication speed                          | 57.6/115.2/<br>230.4 kbit/sec   | 125/250/500<br>kbit/sec                                      | 9.6/19.2/45.45/93.75/<br>187.5/500 kbit/sec<br>1.5/3/6/12 Mbit/sec | 156/625 kbit/sec<br>2.5/5/10 Mbit/sec |  |  |  |  |  |
| Rated voltage                                |                                 | 24 VD0   | C  |                                       |  |  |  |  |  |
| Power supply voltage range                   | '                               | unit power supply: 3<br>supply: 24 VDC + 10%/-               | 24 VDC ± 10%<br>-5% (with power drop wa                            | arning at approx. 20 V)               |  |  |  |  |  |
|  | _                               | supply for DeviceNet<br>11 to 25 VDC                         | _  | _                                     |  |  |  |  |  |
|  | 200 mA or less (single GW unit) |  |  |                                       |  |  |  |  |  |
| Current consumption                          | _                               | Communication power<br>supply for DeviceNet<br>50 mA or less | _  | _                                     |  |  |  |  |  |
| Number of inputs/outputs                     |                                 | Maximum 64 in  | puts/64 outputs  |                                       |  |  |  |  |  |
| Number of input/<br>output branches          | 4 b                             | ranches (16 inputs/  | 16 outputs per brar  | nch)                                  |  |  |  |  |  |
| Branch cable                                 |                                 | 8 core heav  | y duty cable   |                                       |  |  |  |  |  |
| Branch cable length                          | 5                               | m or less (total ext   | tension 10 m or less   | s)                                    |  |  |  |  |  |
| Communication connector                      |                                 | M12 connector  | (8 pins, socket)   |                                       |  |  |  |  |  |
| Power connector                              |                                 | M12 connecto   | r (5 pins, plug)   |                                       |  |  |  |  |  |
| Ambient operating temperature/humidity       | +5 to                           | +45°C at 35% to 85   | 5% RH (no condens  | sation)                               |  |  |  |  |  |
| Enclosure                                    |                                 | IP   | 65   |                                       |  |  |  |  |  |
| Applicable standard                          |                                 | UL, CS   | SA, CE   |                                       |  |  |  |  |  |
| Weight (g)                                   |                                 | 47   | 70   |                                       |  |  |  |  |  |

## Input Block Conforms to IP67


#### **How to Order Input Manifold**





Note) When ordering an input block manifold, enter the Input manifold part no. + Input block part no. together. The input block, end block and DIN rail are included in the input manifold.

## **How to Order Input Block**



# Applicable GW unit DeviceNet PROFIBUS-DP -X1 Remote I/O (RIO) With waterproof cap

#### **Input Unit Specification**

| Connection block            | Current source type input block (PNP input block) or Current sink type input block (NPN input block) |
|-----------------------------|--|
| Communication connector     | M12 connector (8 pins, plug)   |
| Number of connection blocks | Maximum 8 blocks   |
| Block supply voltage        | 24 VDC   |
| Block supply current        | 0.65 A maximum   |
| Current consumption         | 100 mA or less (at rated voltage)  |
| Short circuit protection    | Operates at 1ATyp. (power supply cut) GW unit reset by turning power OFF and back ON.                |
| Enclosure                   | IP65   |
| Weight (g) Note)            | 100 (Input unit + end block)   |

#### Note) Not including the DIN rail weight

## Input Block Specifications


| input Blook opcomoditions |  |  |  |  |  |  |  |  |
|---------------------------|--|--|--|--|--|--|--|--|
| Applicable sensor         | Current source type (PNP output)<br>or<br>Current sink type (NPN output) |  |  |  |  |  |  |  |
| Sensor connector          | M8 connector (3 pins) or, M12 connector (4 pins)                         |  |  |  |  |  |  |  |
| Number of inputs          | 2 inputs/8 inputs (M8 only)  |  |  |  |  |  |  |  |
| Rated voltage             | 24 VDC   |  |  |  |  |  |  |  |
| Indication                | Green LED  |  |  |  |  |  |  |  |
| Insulation                | None   |  |  |  |  |  |  |  |
| Sensor supply current     | Maximum 30 mA/Sensor   |  |  |  |  |  |  |  |
| Enclosure                 | IP65   |  |  |  |  |  |  |  |
| Weight (g)                | [For M8: 20] [For M12: 40] [8 point integrated type, for M8: 55]         |  |  |  |  |  |  |  |





## SI unit

## **How to Order**




## **Specifications**


| Connection block                    | Solenoid valve (single, double) Relay output module (1 output, 2 outputs)                            |  |  |  |  |  |
|-------------------------------------|--|--|--|--|--|--|
| Communication connector             | M12 connector (8-pin, plug, socket)  |  |  |  |  |  |
| Number of connection block stations | Double solenoid valve<br>Relay output module (2 points): Maximum 8 stations<br>Single solenoid valve |  |  |  |  |  |
|                                     | Relay output module (1 point): Maximum 16 stations   |  |  |  |  |  |
| Block supply voltage                | 24 VDC   |  |  |  |  |  |
| Block supply current                | 0.65A maximum  |  |  |  |  |  |
| Current consumption                 | 100mA or less (at rated voltage)   |  |  |  |  |  |
| Weight (g)                          | 115  |  |  |  |  |  |


## **Cables**

**How to Order Cable with M12 Connector** 



**How to Order Power Cable with Connector** 







Socket connector Connections pin arrangement




Plug connector pin arrangement



Socket connector Connections pin arrangement



## VV5QC11 SA1 Kit (Serial Transmission Kit: EX500)



Formulas L1 = 10.5n + 45 (Maximum 16 single wiring stations)


n: Stations

| L_n | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    |
|-----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L1  | 55.5  | 66    | 76.5  | 87    | 97.5  | 108   | 118.5 | 129   | 139.5 | 150   | 160.5 | 171   | 181.5 | 192   | 202.5 | 213   |
| L2  | 104   | 114.5 | 125   | 135.5 | 146   | 156.5 | 167   | 177.5 | 188   | 198.5 | 209   | 219.5 | 230   | 240.5 | 251   | 261.5 |
| L3  | 125   | 137.5 | 150   | 162.5 | 175   | 187.5 | 187.5 | 200   | 212.5 | 225   | 237.5 | 250   | 250   | 262.5 | 275   | 287.5 |
| L4  | 135.5 | 148   | 160.5 | 173   | 185.5 | 198   | 198   | 210.5 | 223   | 235.5 | 248   | 260.5 | 260.5 | 273   | 285.5 | 298   |

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.

## VV5QC21 SA1 Kit

## (Serial Transmission Kit: EX500)




#### Formulas L1 = 16n + 57 (Maximum 16 single wiring stations)

n: Stations

| L  | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L1 | 73    | 89    | 105   | 121   | 137   | 153   | 169   | 185   | 201   | 217   | 233   | 249   | 265   | 281   | 297   | 313   |
| L2 | 118   | 134   | 150   | 166   | 182   | 198   | 214   | 230   | 246   | 262   | 278   | 294   | 310   | 326   | 342   | 358   |
| L3 | 137.5 | 150   | 175   | 187.5 | 200   | 212.5 | 237.5 | 250   | 262.5 | 287.5 | 300   | 312.5 | 337.5 | 350   | 362.5 | 375   |
| L4 | 148   | 160.5 | 185.5 | 198   | 210.5 | 223   | 248   | 260.5 | 273   | 298   | 310.5 | 323   | 348   | 360.5 | 373   | 385.5 |

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.

## VV5QC41 SA1 Kit (Serial Transmission Kit: EX500)



Formulas L1 = 25n + 106 (Maximum 16 single wiring stations)

n: Stations

| L  | 1   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   | 10  | 11  | 12  | 13  | 14  | 15  | 16  |
|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| L1 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 |
| L2 | 177 | 202 | 227 | 252 | 277 | 302 | 327 | 352 | 377 | 402 | 427 | 452 | 477 | 502 | 527 | 552 |



# VQC1000/2000/4000

## Kit (Serial Transmission Kit) for I/O Conforms to IP67

## Compatible network

## DeviceNet/PROFIBUS-DP/CC-Link

• The serial transmission system greatly reduces connection work, minimizes wiring, and saves space.

#### SI unit for DeviceNet/PROFIBUS-DP/CC-Link

As a DeviceNet/PROFIBUS-DP/CC-Link slave unit, this kit is capable of up to 32 points of solenoid valve ON and OFF control.

Furthermore, by connecting an input block, a maximum 32 sensor signal inputs are possible.

#### SI unit for AS-i

As a AS-i slave unit, this kit is capable of up to 4 or 8 points of solenoid valve ON and OFF control.


Furthermore, by connecting an inmput block, a maximun 4 or 8 sensor signal inputs are possible.

#### Input block

This expansion block connects to the SI unit and allows for sensor input to the auto switches.

Each input block can receive input from up to two or four sensors, and the common can be matched to the sensor by an NPN/PNP selector switch. Input connectors are available in both M8 and M12 types.

## Connector Details



#### Circuit diagram Input module (EX250-IE\*)

Input connection: M12 ... 5 pin (Socket)
Example for the cable side connection: OMRON Corporation XS2G; Karl Lumberg GmbH: Series RST5; Franz Binder GmbH: Series 713,763



| Pos. | Description  | Function                 |
|------|--------------|--------------------------|
| 1    | SW+          | Sensor power supply +    |
| 2    | N.C (SIGNAL) | Open*                    |
| 3    | SW-          | Sensor power supply –    |
| 4    | SIGNAL       | Sensor input signal      |
| 5    | E            | Sensor ground connection |

\* In the 4 input type unit (EX250-IE2), this is the input signal from the second sensor connected

#### Communication connector

CANopen: Female connector cable: M12 female 5 pins cable with shield (according to ISO11898).

| Pos. | Description | Function                 |
|------|-------------|--------------------------|
| 1    | CAN_SHLD    | Shield                   |
| 2    | CAN_V+      | Power supply +           |
| 3    | CAN_GND     | Power supply –           |
| 4    | CAN_H       | Bus line (dominant High) |
| 5    | CAN_L       | Bus line (dominant Low)  |



DeviceNet: M12...5 pin (Plug) Example for a cable set with plug / socket: OMRON Corporation DCA1-5CN05F1. Karl Lumberg GmbH: 0935 253 103/...M, RSC RKC 57\* Accessories, bus branch Y: Karl Lumberg GmbH: 0906 UTP 101, Hans Turck GmbH: VB2-FKM-FSM57. Accessories terminating socket with resistor: Hans Turck GmbH: RSE57-TR2, Karl Lumberg GmbH: 0939 CXT 101.

| Pos. | Description | Function               |
|------|-------------|------------------------|
| 1    | Drain       | Drain / shield         |
| 2    | V+          | Circuit power supply + |
| 3    | V-          | Circuit power supply - |
| 4    | CAN_H       | Signal H               |
| 5    | CAN L       | Signal L               |



PROFIBUS-DP: M12... 5 pin reserve-keyed (Socket). Example for the corresponding cable sets with plug / socket: Hans Turck GmbH: RSSW-RKSW456-...M; Karl Lumberg GmbH: 0975 254 101/...M

Accessories Bus branch Y: Hans Turck GmbH: VB2/FSW/FKW/FSW45

Accessories terminating resistor: Hans Turck GmbH: RSS4.5-PDP-TR; Karl Lumberg GmbH: 0979PTX101

| Pos. | Description | Function                               |
|------|-------------|--|
| 1    | VP          | Power supply for terminating resistor  |
| 2    | A-N         | Negative for data transfer / reception |
| 3    | DGND        | Ground for terminating resistor        |
| 4    | B-P         | Positive for data transfer / reception |
| 5    | SHIELD      | Shield                                 |



#### Power supply

**DeviceNet::** M12...5 pin reserve-keyed (Plug) (The configuration of the connection surface area differs from that of the transmission plug) Example of the cable set with socket: Hans Turck GmbH: WAKW4.5T-2, Franz Binder GmbH: 79-4449-..-05

|  | BUS  PWR |  |  |
|--|----------|--|--|

| Pos. Description |   | Description | Function                 |
|------------------|---|-------------|--------------------------|
|                  | 1 | SV24V       | +24V solenoid valve      |
|                  | 2 | SV0V        | 0V solenoid valve        |
|                  | 3 | SW24V       | +24V SI and input blocks |
|                  | 4 | SW0V        | 0V SI and input blocks   |
|                  | 5 | Е           | Ground connection        |



PROFIBUS-DP: M12...5 pin (Plug) Example of the cable set with socket: SMC: EX500-AP...S (see page 16)

| Example for cable side connection: Franz Binder GmbH Series 718, 768 Karl Lumberg GmbH: Series RSMV3 |      |                       |          |
|--|------|-----------------------|----------|
|  | Pos. | Description           | Function |
| 1 SW+ Sensor power   |      | Sensor power supply + |          |

Input connection: M8 ... 3 pin (Socket)



| Pos.  | Description | Function              |
|-------|-------------|-----------------------|
| 1 SW+ |             | Sensor power supply + |
| 3     | SW-         | Sensor power supply - |
| 4     | SIGNAL      | Sensor input signal   |

| _    |             |                          |
|------|-------------|--------------------------|
| Pos. | Description | Function                 |
| 1    | SV24V       | +24V solenoid valve      |
| 2    | SV0V        | 0V solenoid valve        |
| 3    | SW24V       | +24V SI and input blocks |
| 4    | SW0V        | 0V SI and input blocks   |
| 5    | E           | Ground connection        |




#### AS-i EX250-SAS7 / EX250-SAS9

Communication connector: M12 male 4pins



|                       | Pos. | Description | Function                   |
|-----------------------|------|-------------|----------------------------|
| 1 AS-i +<br>2 RESERVE |      | AS-i +      | Positive AS-Interface line |
|                       |      | RESERVE     | RESERVE                    |
|                       | 3    | AS-i –      | Negative AS-Interface line |
|                       | 4    | RESERVE     | RESERVE                    |
|                       | 4    | RESERVE     | RESERVE                    |





#### AS-i EX250-SAS3 / EX250-SAS5

Communication connector: M12 male 4pins




| Pos. | Description | Function                             |             |
|------|-------------|--------------------------------------|-------------|
| 1    | AS-i +      | Positive AS-Interface line           |             |
| 2    | 0V          | Negative output equipment power line | <del></del> |
| 3    | AS-i –      | Negative AS-Interface line           |             |
| 4    | 24V         | Positive output equipment power line | <u></u>     |
|      |             |                                      |             |


#### Output equipment power connector: M12 male 4pins



| Pos. | Description | Function                             |   |
|------|-------------|--------------------------------------|---|
| 1    | 24V         | Positive output equipment power line | _ |
| 2    | NC          | Not connected                        |   |
| 3    | 0V          | Negative output equipment power line | _ |
| 4    | NC          | Not connected                        |   |

\*Connected inside the SI unit.





## **Indicator Unit (LED) Description and Function**


## ■ SI unit

#### DeviceNet (EX250-SDN1)



| Name    | Function   |
|---------|--|
| PWR(V)  | ON when solenoid valve power supply is turned ON.                                    |
| PWR     | ON when DeviceNet circuit power supply input is turned ON.                           |
|         | OFF: Power supply off, off line, or when checking duplication of MAC_ID.             |
|         | GREEN BLINKING: Waiting for connection (on line).                                    |
| MOD/NET | GREEN ON: Connection established (on line).  |
| WOD/NET | RED BLINKING: Connection time out (minor communication abnormality).                 |
|         | RED ON: MAC_ID duplication error, or BUSOFF error (major communication abnormality). |

### ■ Input block (EX250-IE1/2/3)






| Description | Function                           |
|-------------|------------------------------------|
| PWR         | ON when sensor power is turned ON. |
| 0 to 1(3)   | ON when each sensor input goes ON. |



\* Contact your SMC representative for specifications and handling precautions.

### ■ PROFIBUS-DP (EX250-SPR1)



| Name       | Function   |
|------------|--|
| DIA/D() () | GREEN ON when solenoid valve power supply is turned ON.    |
| PWR(V)     | GREEN OFF when the power supply voltage is less than 19 V. |
| RUN        | GREEN ON when operating (SI unit power supply is ON).      |
| DIA        | RED ON when self diagnosis device detects abnormality.     |
| BF         | RED ON for BUS abnormality.                                |

### ■ CC-Link (EX250-SMJ2)



| Name  | Function   |
|-------|--|
| PW    | ON: Input and control unit power supply ON. OFF: Input and control unit power supply OFF.                        |
| PW(V) | ON: Solenoid valve power supply ON. OFF: Solenoid valve power supply voltage is less than 19 V.                  |
| L RUN | ON: Normal traffic OFF: Traffic disconnected (Timeover error)  |
| L ERR | ON: Traffic error BLINKING: Station or baud rate switch is set while the power supply is ON. OFF: Normal traffic |

When the data link is normal, PW, PW (V) and L RUN are ON.

## ■ AS-i (EX250-SAS□)



| Name   | LED<br>Condition | Contents  |
|--------|------------------|---|
| PWR    | Green<br>Light   | In time of power supply for AS-Interface line is turned on.                                 |
| AUX    | Green<br>Light   | In time of auxiliary power supply for output equipment is turned on.                        |
| IN-ERR | Red Light        | In time of input power is detected over current. (Lights off at normal condition)           |
| COM-   | Red Light        | In time of communication error.<br>(Lights off at normal condition)                         |
| ERR    | Red Blink        | In time of peripheral equipment error. (Over current of input power, blowing the fuse etc.) |

## ■ SI unit


## CANopen (EX250-SCA1)



| Name    | LED<br>Condition           | Contents   |  |  |  |  |  |  |
|---------|----------------------------|--|--|--|--|--|--|--|
| PWR(V)  | Green Light                | Illuminates when power for solenoid valves is supplied |  |  |  |  |  |  |
| FVVK(V) | Green Light                | Illuminates when power for CANopen line is supplied    |  |  |  |  |  |  |
| PWR     | Green Light                | Illuminates when SI unit is in the Operational state   |  |  |  |  |  |  |
|         | Green Light (blinking)     | SI unit is in the Pre-Operational state                |  |  |  |  |  |  |
|         | Green Light (single flash) | Single flash when SI unit is in Stopped state          |  |  |  |  |  |  |
| CAN     | Red Light (single flash)   | Single flash when CAN controller error occurs          |  |  |  |  |  |  |
| CAN     | Red Light (double flash)   | Double flash when Error Control Event occurs           |  |  |  |  |  |  |
|         | Green/Red Light            | Flickering when SI unit is in Configuration mode       |  |  |  |  |  |  |
|         | (flickering)               | (LSS services)   |  |  |  |  |  |  |
|         | Red Light                  | Red Light SI unit is in "Bus OFF" state                |  |  |  |  |  |  |



VV5QC11 S Kit (Serial Transmission **Kit: EX250)** 




Formulas

L1 = 10.5n + 45 (Maximum 24 single wiring stations)

L2: For one input block. Add 21 mm for each additional input block

n: Stations 2 3 4 5 6 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 L1 55.5 66 76.5 87 97.5 108 118.5 129 139.5 150 160.5 171 181.5 192 202.5 213 223.5 234 244.5 255 265.5 276 286.5 297 L2 178 188.5 199 209.5 220 230.5 241 251.5 262 272.5 283 293.5 304 314.5 325 335.5 346 356.5 367 377.5 388 398.5 409 419.5 237.5 250 250 262.5 275 287.5 300 312.5 325 325 337.5 350 362.5 375 387.5 387.5 400 412.5 425 437.5 450 260.5 260.5 273 285.5 298 310.2 323 335.5 335.5 348 360.5 373 385.5 398 410.5 423 210.5 223 235.5 248

VV5QC21 S Kit (Serial Transmission **Kit: EX250)** 



Formulas

L1 = 16n + 57 (Maximum 24 single wiring stations) L2: For one input block. Add 21 mm for each additional input block

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.




<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.


n: Stations 4 5 6 8 9 10 12 19 23 24 2 3 11 13 14 15 16 17 18 20 21 22 89 105 137 153 185 217 233 249 265 281 297 313 329 345 361 377 393 409 425 441 L1 73 121 169 201 L2 192 208 224 240 256 288 304 320 336 352 368 384 400 416 432 448 464 480 496 512 528 544 560 272 212.5 237.5 250 13 262.5 275 287.5 312.5 325 337.5 362.5 375 387.5 400 425 437.5 450 462.5 487.5 500 512.5 537.5 550 562.5 587.5 335.5 348 373 L4 248 260.5 273 285.5 298 323 385.5 398 410.5 435.5 448 460.5 473 498 510.5 523 548 560.5 573 598



## VV5QC41 S Kit

## (Serial Transmission Kit: EX250)





Formulas

L1 = 25n + 106 (Maximum 16 single wiring stations)

\* L2: For one input block. Add 21 mm for each additional input block.

| n: Stations |
|-------------|
|-------------|

| L  | 1   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   | 10  | 11  | 12  | 13  | 14  | 15  | 16  |
|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| L1 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 |
| L2 | 230 | 255 | 280 | 305 | 330 | 355 | 380 | 405 | 430 | 455 | 480 | 505 | 530 | 555 | 580 | 605 |





# VQC4000 Kit (Serial Transmission Kit) for I/O Conforms to IP65

## Compatible network | DeviceNet/PROFIBUS-DP

• The serial transmission system greatly reduces connection work, minimizes wiring, and saves space.

#### DeviceNet/PROFIBUS-DP compatible SI unit

As a DeviceNet/PROFIBUS-DP slave unit, this kit is capable of solenoid valve ON and OFF control up to 32 points.

Furthermore, by connecting an input block, up to 32 sensor signal inputs

#### Input block

This expansion block connects to the SI unit and allows for sensor input to the auto switches.

Each input block can receive input from up to 8 sensors, and the common can be matched to the sensor by an NPN/PNP selector switch.

## Connector Details

## Input block SI unit (DeviceNet) SI unit (PROFIBUS-DP) Communication connector Input connector Power connector

• Communication connector (PROFIBUS-DP): CONINVERS® RC-2RS1N12, 12 pins

Cable side connector example: Siemens AG 6ES5 760-2CB11



No. Description

SV24V

| No. | Description | Function                |  |  |  |  |  |  |
|-----|-------------|-------------------------|--|--|--|--|--|--|
| 1   | M5V         | GND Terminal            |  |  |  |  |  |  |
| 2   | Α           | Signal –N               |  |  |  |  |  |  |
| 4   | В           | Signal -P               |  |  |  |  |  |  |
| 6   | +5V         | Terminal +5V            |  |  |  |  |  |  |
| 9   | SHIELD      | Shield ground           |  |  |  |  |  |  |
| 12  | RTS         | Optical fiber (reserve) |  |  |  |  |  |  |

- Pin no. 3, 5, 7, 8, 10 and 11 marked with "●" are open.
- \* The connector configuration and the pin arrangement are compatible with Siemens AG ET200C.
- Input connector: M12, 5 pins (OMRON Corporation XS2F compatible) x 8 pcs.

Cable side connector example: OMRON Corporation XS2G



|   | No. | Description | Function                 |  |  |  |  |
|---|-----|-------------|--------------------------|--|--|--|--|
|   | 1   | SW +        | (+) Sensor power supply  |  |  |  |  |
|   | 2   | N.C.        | Open*                    |  |  |  |  |
| 3 | 3   | SW -        | (-) Sensor power supply  |  |  |  |  |
|   | 4   | SIGNAL      | Sensor input signal      |  |  |  |  |
|   | 5   | PE          | Protective sensor ground |  |  |  |  |

\* The second pin of the connector with input no. 0, 2, 4, 6 (the connector at the right side of the input block) is connected internally to the fourth pin (sensor input no.) of the connector with input no. 1, 3, 5, 7. This makes it possible to directly input two inputs that are combined together by the common connector.

| Connector:    | Input no | Input no. 1, 3, 5, |  |   |  |  |  |
|---------------|----------|--------------------|--|---|--|--|--|
| SW+           |          | 1                  |  | 1 |  |  |  |
| SIGNAL -n + 1 |          | 2                  |  | 2 |  |  |  |
| SW-           |          | 3                  |  | 3 |  |  |  |
| SIGNAL -n     |          | 4                  |  | 4 |  |  |  |
| PE            |          | 5                  |  | 5 |  |  |  |

\* DIN type 5 pins

| 2 | 2 | SV0V  | For solenoid valve +0V  |
|---|---|-------|-------------------------|
| 1 | 3 | PE    | Protective ground       |
|   | 4 | SW24V | For solenoid valve +24V |
|   | 5 | SW0V  | For solenoid valve +0V  |
|   |   |       |                         |

Function

For solenoid valve +24V

• Power connector: Franz Binder GmbH Series723, 5 pins (72309-0115-80-05) Cable side connector example: Franz Binder GmbH 72309-0114-70-15, etc.

• Communication connector (DeviceNet): M12, 5 pins (for DeviceNet only) Example of corresponding cable assemblies with connector: OMRON Corporation DCA1-5CN05F1, Karl Lumberg GmbH & Co. KG RKT5-56.



| No. | Description | Function                              |  |  |  |  |  |
|-----|-------------|---------------------------------------|--|--|--|--|--|
| 1   | Drain       | Drain/Shield (+) Circuit power supply |  |  |  |  |  |
| 2   | V +         |                                       |  |  |  |  |  |
| 3   | V –         | (-) Circuit power supply              |  |  |  |  |  |
| 4   | CAN_H       | Signal H                              |  |  |  |  |  |
| 5   | CAN_L       | Signal L                              |  |  |  |  |  |


Compatible with DeviceNet specification Micro Style connector.

### ⚠ Caution

When IP65 or equivalent enclosures are required, install a waterproof cover on the input connector that is not being used. Order waterproof covers separately


Example: OMRON Corporation XS2Z-12

## Indicator Unit (LED) Descriptions and Functions



| Description | Function   |  |  |  |  |  |
|-------------|--|--|--|--|--|--|
| PWR(V)      | ON when solenoid valve power supply is turned ON.                                    |  |  |  |  |  |
| PWR         | ON when DeviceNet circuit power supply input is turned ON.                           |  |  |  |  |  |
|             | OFF: Power supply off, off line, or when checking duplication of MAC_ID.             |  |  |  |  |  |
|             | GREEN BLINKING: Waiting for connection (on line).                                    |  |  |  |  |  |
| MOD/NET     | GREEN ON: Connection established (on line).  |  |  |  |  |  |
|             | RED BLINKING: Connection time out (minor communication abnormality).                 |  |  |  |  |  |
|             | RED ON: MAC_ID duplication error, or BUSOFF error (major communication abnormality). |  |  |  |  |  |

#### ■ SI unit (PROFIBUS-DP)



| Description | Function  |
|-------------|---|
| PWR(V)      | ON when solenoid valve power supply is turned ON.   |
| PWK(V)      | OFF when the power supply voltage is less than 19V. |
| RUN         | ON when operating (SI unit power supply is ON).     |
| DIA         | ON when self diagnosis device detects abnormality.  |
| BF          | ON for BUS abnormality.                             |


#### Input block




| Description | Function   |
|-------------|--|
|             | ON when sensor power is turned ON. OFF when short circuit protection is working. |
| 0 to 7      | ON when each sensor input goes ON.   |



VV5QC41 S Kit (Serial Transmission Kit: EX240)





|   | Formulas: L1 = 25n + 106, L2 = 25n + 241 (for 1 input block. For each additional input block, add 54mm.) n: Stations (maximum 16 stations) |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |
|---|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
|   | n  | 1   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   | 10  | 11  | 12  | 13  | 14  | 15  | 16  |
| L | .1   | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 |
| L | 2  | 266 | 291 | 316 | 341 | 366 | 391 | 416 | 441 | 466 | 491 | 516 | 541 | 566 | 591 | 616 | 641 |


# S VQC1000/2000/4000 Kit (Serial Transmission Kit) for I/O Conforms to IP67

## **Compatible network**


CC-Link

• The serial transmission system greatly reduces connection work, minimizes wiring, and saves space.

#### **Terminal Block Connection**



Step 2. Wire the cables according to the terminal block specifications below. Pay attention to the wire bound positions



Step 3. How to replace the terminal block cover

Securely tighten the screws to the torque shown in the table below, after confirming that the gasket is installed correctly


Proper tightening torque (N·m)

0.7 to 1.2

- Applicable crimp terminal (fork tongue type): 1.25-3\$, 1.25Y-3
   1.25Y-3N, 1.25Y-3.5
- \* For detailed specifications and handling, refer to the operation manual provided by SMC.


## **Terminal block details**

### • Terminal block LED descriptions



| Description | Function   |
|-------------|--|
| PW          | ON when transmission power supply is ON. OFF when transmission power supply is OFF.                              |
| L RUN       | ON when normal data is received.   |
| SD          | ON when data is sent.  |
| RD          | ON when data is received.  |
| L ERR.      | ON for transmission error and incorrect settings. BLINKING for change in station or transmission speed settings. |

#### Cable wiring




#### Note


 CC-Link system Master unit: AJ61BT11 Master unit: AJ51BT11 Master unit: AJ61QBT11 Master unit: AJ61QBT11

• 16 outputs



VV5QC11 S Kit (Serial Transmission Kit: EX126)





Formulas

L1 = 10.5n + 45 (Maximum 16 single wiring stations)

L2 = 10.5n + 154.5

n: Stations


| L | ,<br>_s | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    |
|---|---------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
|   | L1      | 55.5  | 66    | 76.5  | 87    | 97.5  | 108   | 118.5 | 129   | 139.5 | 150   | 160.5 | 171   | 181.5 | 192   | 202.5 | 213   |
|   | L2      | 165   | 175.5 | 186   | 196.5 | 207   | 217.5 | 228   | 238.5 | 249   | 259.5 | 270   | 280.5 | 291   | 301.5 | 312   | 322.5 |
|   | L3      | 187.5 | 200   | 212.5 | 212.5 | 225   | 237.5 | 250   | 262.5 | 275   | 275   | 287.5 | 300   | 312.5 | 325   | 337.5 | 337.5 |
|   | L4      | 198   | 210.5 | 223   | 223   | 235.5 | 248   | 260.5 | 273   | 285.5 | 285.5 | 298   | 310.5 | 323   | 335.5 | 348   | 348   |

\* With signal cut block, L4 is obtained by adding approximately 30 mm to L2.

# S VQC1000/2000/4000 Kit (Serial Transmission Kit) for I/O Conforms to IP67

#### VV5QC21 S Kit

(Serial Transmission Kit: EX126)



#### Formulas


L1 = 16n + 57 (Maximum 16 single wiring stations) L2 = 16n + 163


n: Stations

 $\sqrt{n}$ L1 L2 L3 212.5 237.5 262.5 262.5 287.5 312.5 362.5 408.5 412.5 437.5 L4 210.5 335.5 360.5 385.5 435.5 

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.

VV5QC41 S Kit (Serial Transmission Kit: EX126)






L1 = 25n + 106 (Maximum 16 single wiring stations) L2 = 25n + 192

n: Stations

| L | n  | 1   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   | 10  | 11  | 12  | 13  | 14  | 15  | 16  |
|---|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| L | _1 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 |
| L | _2 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 |

# VQC1000/2000/4000

Kit (D-sub Connector Kit) Conforms to IP40



- We use a D-sub connector (25P) that conforms to MIL standards and is therefore widely compatible with many standard commercial models.
- Top or side entry for the connector can be changed freely, allowing for changes even after mounting, to meet any changing needs for space.

#### **Electrical wiring specifications**

#### **D-sub connector**

Ō

Station 1

Station 2

Station 3

Station 4

Station 5

Station 6

Station 7

Station 8 -

Station 9 <

Station 10

Station 11

Station 12

As the standard electrical wiring specification used is for 12 stations or less, double wiring (connected to SOL. A and SOL. B) is used for 140 01 150 03 160 04 170 05 180 05 190 07 200 07 210 08 220 010 230 011 240 012 250 012 the internal wiring of each station regardless of valve and option types. Mixed single and double wiring are available

Refer to special wiring specifications (options)

Connector terminal no.

#### Terminal Polarity SOL. A

#### Lead wire colours according to pin numbers

The colour code is according to


| OL B  | 1  | (–) | (+) | DIN47100. |              |                |
|-------|----|-----|-----|-----------|--------------|----------------|
| OL. B | 14 | (-) | (+) | Pin no.   | Cable colour | Identification |
| OL. A | 2  | (-) | (+) | 1         | white        |                |
| OL. B | 15 | (-) | (+) | 2         | brown        | -              |
| OL. A | 3  | (-) | (+) | 3         | green        | _              |
| OL. B | 16 |     |     | 4         | yellow       | -              |
| OL. A | 4  | (-) | (+) | 5         | grey         | _              |
| OL B  | 4  | (–) | (+) | 6         | pink         | _              |
| OL. B | 17 | (–) | (+) | 7         | blue         | _              |
| OL. A | 5  | (-) | (+) | 8         | red          | _              |
| OL. B | 18 | (-) | (+) | 9         | black        |                |
| OL. A | 6  | (-) | (+) | 10        | violet       | _              |
| OL. B | 10 |     |     | 11        | grey         | pink           |
| OL. A | -  | (-) | (+) | 12        | red          | blue           |
| OL. B | 7  | (–) | (+) | 13        | white        | green          |
| ·OL A | 20 | (–) | (+) | 14        | brown        | green          |
| OL. A | 8  | (-) | (+) | 15        | white        | yellow         |
| OL. B | 21 | (-) | (+) | 16        | yellow       | brown          |
| OL. A | 9  | (-) | (+) | 17        | white        | grey           |
| OL. B | 22 | (-) | (+) | 18        | grey         | brown          |
| OL. A | 10 |     |     | 19        | white        | pink           |
| OL. B | 10 | (–) | (+) | 20        | pink         | brown          |
| OL A  | 23 | (–) | (+) | 21        | white        | blue           |
| OL. A | 11 | (–) | (+) | 22        | brown        | blue           |
| OL. B | 24 | (-) | (+) | 23        | white        | red            |
| OL. A | 12 | (-) | (+) | 24        | brown        | red            |
| OL. B | 25 | (-) | (+) | 25        | white        | black          |
| :OM   |    | ( ) | ( ) |           |              |                |

COM ○ 13

Note) When using the negative COM specification for VQC1000/2000, use valves for negative COM.

#### Special wiring specifications (options)

(For 25P)



Mixed single and double wiring are available as options. The maximum number of manifold stations is determined by the number of solenoids. Count one point for a single solenoid type and two points for a double solenoid type. The total number of solenoids (points) must not exceed 24.

#### Cable assembly

#### ■ D-sub connector cable assembly (25 pin)


#### **GVVZS3000-21A-**□

D sub connector / cable

| Cable length (L) | Part no.          | Plug type  |
|------------------|-------------------|------------|
| 1m               | GVVZS3000-21A-160 | 60° outlet |
| 3m               | GVVZS3000-21A-260 | 60° outlet |
| 5m               | GVVZS3000-21A-360 | 60° outlet |
| 8m               | GVVZS3000-21A-460 | 60° outlet |
| 3m               | GVVZS3000-21A-2   | Standard   |
| 5m               | GVVZS3000-21A-3   | Standard   |
| 8m               | GVVZS3000-21A-4   | Standard   |

#### Shielded cable

| Cable length (L) | Part no.         | Cable type |
|------------------|------------------|------------|
| 1m               | GVVZS3000-21A-1S | shielded   |
| 3m               | GVVZS3000-21A-2S | shielded   |
| 5m               | GVVZS3000-21A-3S | shielded   |
| 8m               | GVVZS3000-21A-4S | shielded   |
| 20m              | GVVZS3000-21A-5S | on demand  |



#### **Electrical** characteristics


| ona aotoriotico                 |                      |
|---------------------------------|----------------------|
| Item                            | Charac-<br>teristics |
| Conductor resistence Ω/km, 20°C | 57 or less           |
| Electric strength V, 5min, AC   | 1500                 |
| Insulation resistence MΩ/km     | 20                   |

#### Standard version

(See also AXT100-DS25 which conforms to colour code MIL-C24308)

\* For detailed specifications and handling, please contact SMC.





Formulas L1 = 10.5n + 45 (Maximum 24 single wiring stations)

L2 = 10.5n + 102


| L  | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    | 17    | 18    | 19    | 20    | 21    | 22    | 23    | 24    |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L1 | 55.5  | 66    | 76.5  | 87    | 97.5  | 108   | 118.5 | 129   | 139.5 | 150   | 160.5 | 171   | 181.5 | 192   | 202.5 | 213   | 223.5 | 234   | 244.5 | 255   | 265.5 | 276   | 286.5 | 297   |
| L2 | 112.5 | 123   | 133.5 | 144   | 154.5 | 165   | 175.5 | 186   | 196.5 | 207   | 217.5 | 228   | 238.5 | 249   | 259.5 | 270   | 280.5 | 291   | 301.5 | 312   | 322.5 | 333   | 343.5 | 354   |
| L3 | 137.5 | 150   | 162.5 | 175   | 175   | 187.5 | 200   | 212.5 | 225   | 237.5 | 237.5 | 250   | 262.5 | 275   | 287.5 | 300   | 300   | 312.5 | 325   | 337.5 | 350   | 362.5 | 375   | 375   |
| L4 | 148   | 160.5 | 173   | 185.5 | 185.5 | 198   | 210.5 | 223   | 235.5 | 248   | 248   | 260.5 | 273   | 285.5 | 298   | 310.5 | 310.5 | 323   | 335.5 | 348   | 360.5 | 373   | 385.5 | 385.5 |

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.



n: Stations





Formulas

L1 = 16n + 57 (Maximum 24 single wiring stations)


L2 = 16n + 110.5

n: Stations

| L  | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    | 17    | 18    | 19    | 20    | 21    | 22    | 23    | 24    |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L1 | 73    | 89    | 105   | 121   | 137   | 153   | 169   | 185   | 201   | 217   | 233   | 249   | 265   | 281   | 297   | 313   | 329   | 345   | 361   | 377   | 393   | 409   | 425   | 441   |
| L2 | 126.5 | 142.5 | 158.5 | 174.5 | 190.5 | 206.5 | 222.5 | 238.5 | 254.5 | 270.5 | 286.5 | 302.5 | 318.5 | 334.5 | 350.5 | 366.5 | 382.5 | 398.5 | 414.5 | 430.5 | 446.5 | 462.5 | 478.5 | 494.5 |
| L3 | 150   | 162.5 | 187.5 | 200   | 212.5 | 237.5 | 250   | 262.5 | 275   | 300   | 312.5 | 325   | 350   | 362.5 | 375   | 387.5 | 412.5 | 425   | 437.5 | 450   | 475   | 487.5 | 500   | 525   |
| L4 | 160.5 | 173   | 198   | 210.5 | 223   | 248   | 260.5 | 273   | 285.5 | 310.5 | 323   | 335.5 | 360.5 | 373   | 385.5 | 398   | 423   | 435.5 | 448   | 460.5 | 485.5 | 498   | 510.5 | 535.5 |

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.






Formulas L1 = 25n + 106 (Maximum 16 single wiring stations) L2 = 25n + 139.5


n: Stations 164.5 189.5 214.5 239.5 264.5 289.5 314.5 339.5 364.5 389.5 414.5 439.5 464.5 489.5 514.5 539.5

# VQC1000/2000/4000 Kit (Flat Ribbon Cable Kit) Conforms to IP40

- Using our flat ribbon cable for electrical connections greatly reduces labour, while it also minimizes wiring and saves space.
- We use flat ribbon cables whose connectors (26P and 20P) conform to MIL standards, and are therefore widely compatible with many standard commercial models.
- Top or side entry for the connector can be changed freely, allowing for changes even after mounting, to meet any changing needs for space.

#### **Electrical wiring specifications**






#### Cable assembly

# AXT100-FC 20 - 2

Type 26P flat ribbon cable connector assemblies can be ordered with manifolds. Refer to manifold ordering.



#### Flat ribbon cable connector assemblies (optional)


| Cable      | Part          | no.           |
|------------|---------------|---------------|
| length (L) | 26P           | 20P           |
| 1.5m       | AXT100-FC26-1 | AXT100-FC20-1 |
| 3m         | AXT100-FC26-2 | AXT100-FC20-2 |
| 5m         | AXT100-FC26-3 | AXT100-FC20-3 |

- When using a standard commercial connector, use a type 26P connector conforming to MIL-C-83503 or a type 20P with strain relief.
- \* Cannot be used for transfer wiring.

#### Some connector manufacturers:


- HIROSE ELECTRIC CO., LTD.
- Sumitomo/3-M Limited
- Fujitsu, Ltd.
- Japan Aviation Electronics Industry, Ltd.
- J.S.T. Mfg. Co., Ltd.
- Oki Electric Cable Co., Ltd.

#### **Special wiring specifications (options)**



Mixed single and double wiring are available as options. The maximum number of manifold stations is determined by the number of solenoids. Count one point for a single solenoid type and two points for a double solenoid type. The total number of solenoids (points) must not exceed 24.

37



Formulas

L1 = 10.5n + 45 (Maximum 24 single wiring stations


| L1 = 10.5n + 45  | (Iviaximum 24 singi | e wiring | stations |
|------------------|---------------------|----------|----------|
| L2 = 10.5n + 102 |                     |          |          |

|   |    |       |       |       |       |       |       |       |       |       |       |       |       | L2 = ' | 10.5n <del>1</del> | - 102 |       |       |       |       |       |       |       | n: 51 | tations |
|---|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|--------|--------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| ĺ | L  | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13     | 14                 | 15    | 16    | 17    | 18    | 19    | 20    | 21    | 22    | 23    | 24      |
|   | L1 | 55.5  | 66    | 76.5  | 87    | 97.5  | 108   | 118.5 | 129   | 139.5 | 150   | 160.5 | 171   | 181.5  | 192                | 202.5 | 213   | 223.5 | 234   | 244.5 | 255   | 265.5 | 276   | 286.5 | 297     |
|   | L2 | 112.5 | 123   | 133.5 | 144   | 154.5 | 165   | 175.5 | 186   | 196.5 | 207   | 217.5 | 228   | 238.5  | 249                | 259.5 | 270   | 280.5 | 291   | 301.5 | 312   | 322.5 | 333   | 343.5 | 354     |
|   | L3 | 137.5 | 150   | 162.5 | 175   | 175   | 187.5 | 200   | 212.5 | 225   | 237.5 | 237.5 | 250   | 262.5  | 275                | 287.5 | 300   | 300   | 312.5 | 325   | 337.5 | 350   | 362.5 | 375   | 375     |
|   | L4 | 148   | 160.5 | 173   | 185.5 | 185.5 | 198   | 210.5 | 223   | 235.5 | 248   | 248   | 260.5 | 273    | 285.5              | 298   | 310.5 | 310.5 | 323   | 335.5 | 348   | 360.5 | 373   | 385.5 | 385.5   |

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.







10

300 312.5 325

217 233 249

12

Formulas L1 = 16n + 57 (Maximum 24 single wiring stations)

L2 = 16n + 110.5

|    | 13    | 14    | 15    | 16    | 17    | 18    | 19    | 20    | 21    | 22    | 23    | 24    |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
|    | 265   | 281   | 297   | 313   | 329   | 345   | 361   | 377   | 393   | 409   | 425   | 441   |
| .5 | 318.5 | 334.5 | 350.5 | 366.5 | 382.5 | 398.5 | 414.5 | 430.5 | 446.5 | 462.5 | 478.5 | 494.5 |

350 362.5 375 387.5 412.5 425 437.5 450 475 487.5 500

n: Stations

126.5 142.5 158.5 174.5 190.5 206.5 222.5 238.5 254.5 270.5 286.5 302. 212.5 237.5 250

185 201

262.5 275

6

5

137 153 169



L1

L2

L3

2 3


89

105 121

162.5 187.5 200

73

<sup>160.5 173 198</sup> 210.5 223 248 260.5 273 285.5 310.5 323 335.5 360.5 373 385.5 398 423 435.5 448 460.5 485.5 498 510.5 535.5 \* With signal cut block, L4 is obtained by adding approximately 30 mm to L2.




Formulas L1 = 25n + 106 (Maximum 16 single wiring stations) L2 = 25n + 139.5

n: Stations

| L  | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L1 | 131   | 156   | 181   | 206   | 231   | 256   | 281   | 306   | 331   | 356   | 381   | 406   | 431   | 456   | 481   | 506   |
| L2 | 164.5 | 189.5 | 214.5 | 239.5 | 264.5 | 289.5 | 314.5 | 339.5 | 364.5 | 389.5 | 414.5 | 439.5 | 464.5 | 489.5 | 514.5 | 539.5 |


• This kit has a small terminal block inside a junction box. The provision of a G3/4 electrical entry allows connection of conduit fittings.



#### **Terminal Block Connection**

#### Step 1. How to remove terminal block cover

Loosen the 4 mounting screws (M4) and remove the terminal block cover.




Step 3. How to replace the terminal block cover

Securely tighten the screws to the torque shown in the table below, after confirming that the gasket is installed correctly

Proper tightening torque (N·m) 0.7 to 1.2


#### Step 2. The diagram below shows the terminal block wiring. All stations are provided with double wiring regardless of the valves which are mounted.

Connect each wire to the power supply side, according to the markings provided inside the terminal block.



• Applicable crimp terminal (fork tongue type): 1.25-3S, 1.25Y-3 1.25Y-3N, 1.25Y-3.5

#### Electrical wiring specifications (conforms to IP67)



#### Special wiring specifications (options)


Mixed single and double wiring are available as options. The maximum number of manifold stations is determined by the number of solenoids. Count one point for a single solenoid type and two points for a double solenoid type. The total number of solenoids (points) must not exceed 20.

#### 1. How to order


Indicate option symbol "-K" in the manifold part number and be sure to specify station positions for single or double wiring on the manifold specification

#### 2. Wiring specifications

Connector terminal numbers are connected from solenoid station 1 on the A side in the order indicated by the arrows without skipping any terminal numbers.







Formulas L1 = 10.5n + 45 (Maximum 20 single wiring stations) L2 = 10.5n + 154.5


n: Stations

| L_n | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    | 17    | 18    | 19    | 20    |
|-----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L1  | 55.5  | 66    | 76.5  | 87    | 97.5  | 108   | 118.5 | 129   | 139.5 | 150   | 160.5 | 171   | 181.5 | 192   | 202.5 | 213   | 223.5 | 234   | 244.5 | 255   |
| L2  | 165   | 175.5 | 186   | 196.5 | 207   | 217.5 | 228   | 238.5 | 249   | 259.5 | 270   | 280.5 | 291   | 301.5 | 312   | 322.5 | 333   | 343.5 | 354   | 364.5 |
| L3  | 187.5 | 200   | 212.5 | 212.5 | 225   | 237.5 | 250   | 262.5 | 275   | 275   | 287.5 | 300   | 312.5 | 325   | 337.5 | 337.5 | 350   | 362.5 | 375   | 387.5 |
| L4  | 198   | 210.5 | 223   | 223   | 235.5 | 248   | 260.5 | 273   | 285.5 | 285.5 | 298   | 310.5 | 323   | 335.5 | 348   | 348   | 360.5 | 373   | 385.5 | 398   |

\* With signal cut block, L4 is obtained by adding approximately 30 mm to L2.







Formulas

L1 = 16n + 57 (Maximum 20 single wiring stations)


| L1 = 160 + 57  | (Iviaximum 20 | single | wirin |
|----------------|---------------|--------|-------|
| L2 = 16n + 163 |               |        |       |

| n: | Stat | ion |
|----|------|-----|

| L  | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    | 17    | 18    | 19    | 20    |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L1 | 73    | 89    | 105   | 121   | 137   | 153   | 169   | 185   | 201   | 217   | 233   | 249   | 265   | 281   | 297   | 313   | 329   | 345   | 361   | 377   |
| L2 | 179   | 195   | 211   | 227   | 243   | 259   | 275   | 291   | 307   | 323   | 339   | 355   | 371   | 387   | 403   | 419   | 435   | 451   | 467   | 483   |
| L3 | 200   | 212.5 | 237.5 | 237.5 | 262.5 | 262.5 | 287.5 | 312.5 | 325   | 371   | 362.5 | 375   | 408.5 | 412.5 | 425   | 437.5 | 462.5 | 496   | 487.5 | 500   |
| L4 | 210.5 | 223   | 248   | 248   | 273   | 273   | 298   | 323   | 335.5 | 360.5 | 373   | 385.5 | 398   | 423   | 435.5 | 448   | 473   | 485.5 | 498   | 510.5 |

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.






Formulas L1 = 25n + 106 (Maximum 16 single wiring stations) L2 = 25n + 192

n: Stations

| L  | 1   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   | 10  | 11  | 12  | 13  | 14  | 15  | 16  |
|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| L1 | 131 | 156 | 181 | 206 | 231 | 256 | 281 | 306 | 331 | 356 | 381 | 406 | 431 | 456 | 481 | 506 |
| L2 | 217 | 242 | 267 | 292 | 317 | 342 | 367 | 392 | 417 | 442 | 467 | 492 | 517 | 542 | 567 | 592 |


# VQC1000/2000/4000 Kit (Lead Wire Kit) Conforms to IP67

- Direct electrical entry type.
- IP67 enclosure is available with use of cables with sheath and waterproof connectors.



#### **Electrical wiring specifications**

#### Lead wire specification



As the standard electrical wiring specification used is for 12 stations or less, double wiring (connected to SOL. A and SOL. B) is used for the internal wiring of each station regardless of valve and option types. Mixed single and double wiring are available as options.

Refer to special wiring specifications (options) below.

Colour: Urban white

|              | Termi<br>no.                          |                           | olarity L | ead wire colour | Dot<br>marking |
|--------------|---------------------------------------|---------------------------|-----------|-----------------|----------------|
| Station 1 {  | SOL. A                                | (-)                       | (+)       | Black           | None           |
| Station 1    | SOL. B                                | (-)                       | (+)       | Yellow          | Black          |
| Station 2    | SOL. A 2                              | (-)                       | (+)       | Brown           | None           |
| Station 2    | SOL. B 15                             | (-)                       | (+)       | Pink            | Black          |
| Station 3    | SOL. A                                | (-)                       | (+)       | Red             | None           |
| Station 3    | SOL. B 16                             | (-)                       | (+)       | Blue            | White          |
| Station 4 {  | SOL. A                                | (-)                       | (+)       | Orange          | None           |
| Station 4    | SOL. B 17                             | (-)                       | (+)       | Purple          | None           |
| Station 5 {  | SOL. A <sub>o</sub> 5                 | (-)                       | (+)       | Yellow          | None           |
| Otation 5    | SOL. B 0 18                           | (-)                       | (+)       | Grey            | None           |
| Station 6    | SOL. A                                | (-)                       | (+)       | Pink            | None           |
| Cialion      | SOL. B 19                             | (-)                       | (+)       | Orange          | Black          |
| Station 7    | SOL. A                                | (-)                       | (+)       | Blue            | None           |
|              | SOL. B 20                             | (-)                       | (+)       | Red             | White          |
| Station 8    | SOL. A                                | (-)                       | (+)       | Purple          | White          |
|              | SOL. B 21                             | (-)                       | (+)       | Brown           | White          |
| Station 9 {  | SOL. A                                | (-)                       | (+)       | Grey            | Black          |
|              | SOL. B 22                             | (-)                       | (+)       | Pink            | Red            |
| Station 10 { | SOL. A 0 10                           | (-)                       | (+)       | White           | Black          |
|              | SOL. B 0 23                           | (-)                       | (+)       | Grey            | Red            |
| Station 11   | SOL. A o 11                           | (-)                       | (+)       | White           | Red            |
| [            | SOL. B                                | (-)                       | (+)       | Black           | White          |
| Station 12 { | SOL. A 12                             | (-)                       | (+)       | Yellow          | Red            |
| (            | SOL. B 25                             | (–)                       | (+)       | White           | None           |
|              | COM. 0 13                             | (+)                       | (-) Note) | Orange          | Red            |
|              |                                       | Positive<br>COM.<br>spec. |           |                 |                |
| Note         | When using the negural valves for neg |                           |           | ation for \     | VQC1000/200    |

#### Lead wire length


VV5QC11-08 C6 LD 0

Lead wire length

| 0 | 0.6m |
|---|------|
| 1 | 1.5m |
| 2 | 3.0m |

#### **Electrical characteristics**


| Item                               | Characteristic |
|------------------------------------|----------------|
| Conductor resistance Ω/km, 20°C    | 65 or less     |
| Withstand pressure V, 1 minute, AC | 1000           |
| Insulation resistance MΩ/km, 20°C  | 5 or more      |




#### Special wiring specifications (options)

Mixed single and double wiring are available as options. The maximum number of manifold stations is determined by the number of solenoids. Count one point for a single solenoid type and two points for a double solenoid type. The total number of solenoids (points) must not exceed 24.








Formulas L1 = 10.5n + 45 (Maximum 24 single wiring stations) L2 = 10.5n + 102

n: Stations

|    |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       |       | _     |       |
|----|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| L  | 1     | 2     | 3     | 4     | 5     | 6     | 7     | 8     | 9     | 10    | 11    | 12    | 13    | 14    | 15    | 16    | 17    | 18    | 19    | 20    | 21    | 22    | 23    | 24    |
| L1 | 55.5  | 66    | 76.5  | 87    | 97.5  | 108   | 118.5 | 129   | 139.5 | 150   | 160.5 | 171   | 181.5 | 192   | 202.5 | 213   | 223.5 | 234   | 244.5 | 255   | 265.5 | 276   | 286.5 | 297   |
| L2 | 112.5 | 123   | 133.5 | 144   | 154.5 | 165   | 175.5 | 186   | 196.5 | 207   | 217.5 | 228   | 238.5 | 249   | 259.5 | 270   | 280.5 | 291   | 301.5 | 312   | 322.5 | 333   | 343.5 | 354   |
| L3 | 137.5 | 150   | 162.5 | 175   | 175   | 187.5 | 200   | 212.5 | 225   | 237.5 | 237.5 | 250   | 262.5 | 275   | 287.5 | 300   | 300   | 312.5 | 325   | 337.5 | 350   | 362.5 | 375   | 375   |
| L4 | 148   | 160.5 | 173   | 185.5 | 185.5 | 198   | 210.5 | 223   | 235.5 | 248   | 248   | 260.5 | 273   | 285.5 | 298   | 310.5 | 310.5 | 323   | 335.5 | 348   | 360.5 | 373   | 385.5 | 385.5 |

<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.





| Formulas      |                                     |
|---------------|-------------------------------------|
| L1 = 16n + 57 | (Maximum 24 single wiring stations) |

n: Stations L2 = 16n + 110.5 L1 142.5 158.5 174.5 190.5 206.5 222.5 238.5 254.5 270.5 | 286.5 | 302.5 | 318.5 | 334.5 | 350.5 | 366.5 | 382.5 | 398.5 | 414.5 | 430.5 | 446.5 | 462.5 | 478.5 | 494.5 L3 162.5 187.5 200 212.5 237.5 250 262.5 275 300 312.5 325 350 362.5 375 387.5 412.5 425 437.5 450 475 487.5 500 525 160.5 173 198 210.5 223 248 260.5 273 285.5 310.5 323 335.5 360.5 373 385.5 398 435.5 448 460.5 485.5 498 510.5 535.5




<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.

#### VV5QC41 2-Rc3/4 3(R) port 2-Rc1/2 1(P) port 12 20.5 3.5 72 95.5 000000 (6.5)2-Rc1/8 2-Rc1/8 27 31 External pilot port Pilot exhaust port 38.7 2n-Rc 1/4, 3/8, C8, C10, C12 <4(A), 2(B) port> Rc 1/4:1/4" Female thread Rc 3/8: 3/8" Female thread P=25 C8 : ø8 One-touch fitting C10 : Ø10 One-touch fitting C12 : Ø12 One-touch fitting Indicator light Manual override 48 L1 6.5 P=25 65.5 6 143 74.5 Lead wire length 0.6m,1.5m,3m D-side (Stations) 1 - (2) - (3) - (4) - (5) - (6) - (7) - (8) - (n) [U-side] Formulas L1 = 25n + 106 (Maximum 16 single wiring stations) L2 = 25n + 160.5 n: Stations 16 2 3 5 6 15 131 156 181 206 231 256 281 306 331 356 381 406 431 506

185.5 | 210.5 | 235.5 | 260.5 | 285.5 | 310.5 | 335.5 | 360.5 | 385.5 | 410.5 | 435.5 | 460.5 | 485.5 | 510.5 | 535.5 | 560.5

# VQC1000/2000/4000 Kit (Multiple Connector Kit) Conforms to IP67

- Use of multiple connectors helps streamline wiring procedure to save labour.
- IP67 enclosure is available with use of waterproof multiple connectors.




#### **Electrical wiring specifications**

#### **Multiple connector**



Double wiring(connected to SOL.A and SOL.B) is used for the internal wiring of each staion regardless of valve and option types. Mixed single and double wiring are available as options. Refer to special wiring specifications(options) below.

#### Terminal Polarity



Note) When using the negative COM specification for VQC1000/2000, use valves for negative COM.


# Special wiring specifications (options)

Mixed single and double wiring are available as an option. The maximum number of manifold stations is determined by the number of solenoids. Count one point for a single solenoid type and two points for a double solenoid type. The total number of solenoids (points) must not exceed 24.

#### Cable assembly

## ■ Circular connector cable assembly (26 pin)

#### GAXT100 – MC26 – □



#### Port cable length

| Part no.         | L dimension |
|------------------|-------------|
| GAXT100-MC26-015 | 1.5m        |
| GAXT100-MC26-030 | 3m          |
| GAXT100-MC26-050 | 5m          |

#### Lead wire colours according to pin numbers

The colour code is according to DIN47100.

| Pin no. | Cable colour | Identification |
|---------|--------------|----------------|
| 1       | white        | _              |
| 3       | brown        | _              |
| 3       | green        | _              |
| 4       | yellow       | -              |
| 5       | grey         | _              |
| 6       | pink         | _              |
| 7       | blue         | -              |
| 8       | red          | ı              |
| 9       | black        | -              |
| 10      | violet       | _              |
| 11      | grey         | pink           |
| 12      | red          | blue           |
| 13      | white        | green          |
| 14      | brown        | green          |
| 15      | white        | yellow         |
| 16      | yellow       | brown          |
| 17      | white        | grey           |
| 18      | grey         | brown          |
| 19      | white        | pink           |
| 20      | pink         | brown          |
| 21      | white        | blue           |
| 22      | brown        | blue           |
| 23      | white        | red            |
| 24      | brown        | red            |
| 25      | white        | black          |
| 26 *    | bridg        | ed to pin 25   |

Connector pin number

(Arrangement as seen from the cable's port

side)



#### **Electrical** characteristics


| ondi dotoi istios                       |                      |  |  |  |  |  |
|---|----------------------|--|--|--|--|--|
| Item                                    | Charac-<br>teristics |  |  |  |  |  |
| Conductor resistence $\Omega/km$ , 20°C | 57 or less           |  |  |  |  |  |
| Electric strength V, 5min, AC           | 1500                 |  |  |  |  |  |
| Insulation resistence MΩ/km             | 20                   |  |  |  |  |  |

<sup>\*</sup> only for circular connectors

#### (See also AXT100-MC26-015 which conforms to colour code MIL-C24308)

\* For detailed specifications and handling, please contact SMC.

49




Formulas L1 = 10.5n + 45 (Maximum 24 single wiring stations) L2 = 10.5n + 102

n: Stations 3 10 12 22 23 24 2 5 6 8 9 11 13 14 15 16 17 18 19 20 21 L1 55.5 76.5 87 97.5 108 118.5 129 139.5 150 160.5 171 181.5 192 244.5 255 265.5 276 286.5 297 66 202.5 213 223.5 234 112.5 123 L2 133.5 144 175.5 186 196.5 207 217.5 228 238.5 249 259.5 270 301.5 312 322.5 333 343.5 354 154.5 165 280.5 291 187.5 200 212.5 225 237.5 237.5 250 262.5 275 287.5 300 L3 137.5 150 162.5 175 175 300 312.5 325 337.5 350 362.5 375 375 235.5 248 248 260.5 273 285.5 298 310.5 310.5 323 185.5 185.5 198 210.5 223 335.5 348 360.5 373 385.5 385.5

 $<sup>\</sup>ast$  With signal cut block, L4 is obtained by adding approximately 30 mm to L2.

# VQC1000/2000/4000 Kit (Multiple Connector Kit) Conforms to IP67



Formulas L1 = 16n + 57 (Maximum 24 single wiring stations)

L2 = 16n + 110.5n: Stations L1 126.5 | 142.5 | 158.5 | 174.5 | 190.5 | 206.5 | 222.5 | 238.5 | 254.5 | 270.5 | 286.5 | 302.5 | 318.5 | 334.5 | 350.5 | 366.5 | 382.5 | 398.5 | 414.5 | 430.5 | 446.5 | 462.5 | 478.5 | 494.5 | L2 162.5 187.5 200 212.5 237.5 250 262.5 275 300 312.5 325 350 362.5 375 L3 387.5 412.5 425 437.5 450 475 487.5 500 525 160.5 173 198 210.5 223 248 260.5 273 285.5 310.5 323 335.5 360.5 373 385.5 398 435.5 448 460.5 485.5 498




<sup>\*</sup> With signal cut block, L4 is obtained by adding approximately 30 mm to L2.

#### VV5QC41 2-Rc 3/4 3(R) port Circular multiple connectors (26 pins) 2-Rc 1/2 made by CONINVERS® 1(P) port M27 male screw 2 2 2 95. 9 (6.5)2-Rc1/8 27 31 2-Rc1/8 External pilot port Pilot exhaust port 38.7 2n-Rc 1/4, 3/8, C8, C10, C12 <4(A), 2(B) port> Rc 1/4: 1/4" Female thread P=25 65.5 Rc 3/8: 3/8" Female thread C8 : ø8 One-touch fitting C10 : Ø10 One-touch fitting C12 : Ø12 One-touch fitting Indicator light Manual override 48 6.5 65.5 P=25 143 163 Ŋ 74. 9 D-side Stations 1 2 - 3 - 4 - 5 - 6 - 7 - 8 - - n U-side Multiple connector cable assembly

L1 = 25n + 106 (Maximum 16 single wiring stations) L2 = 25n + 160.5n: Stations \_\_n 15 16 2 3 5 6 9 10 11 12 13 14 181 206 231 256 281 306 331 356 381 406 431 456 L1 131 156 481 506 185.5 210.5 235.5 260.5 285.5 310.5 335.5 360.5 385.5 410.5 435.5 460.5 485.5 510.5 535.5 560.5

Formulas


# Manifold Exploded View



#### Manifold Assembly Part No.


#### Housing assembly and SI unit/Input block

| No.  | Description                          | Part no.         | Note                                  | 1       | Applicable model |         |  |  |
|------|--------------------------------------|------------------|---------------------------------------|---------|------------------|---------|--|--|
| INO. | Description                          | Part IIU.        | Note                                  | VQC1000 | VQC2000          | VQC4000 |  |  |
|      |                                      | EX250-SPR1       | PROFIBUS-DP (-COM.)                   | •       | •                | •       |  |  |
|      |                                      | EX250-SAS□       | AS-i (-COM.)                          | •       | •                | •       |  |  |
| 1    | SI unit                              | EX250-SMJ        | CC-Link (+COM.)                       | •       | •                | •       |  |  |
|      |                                      | EX250-SDN1       | DeviceNet (-COM.)                     | •       | •                | •       |  |  |
|      |                                      | EX250-SCA1       | CANopen (-COM.)                       | •       | •                | •       |  |  |
|      |                                      | EX250-IE1        | M12, 2 inputs                         | •       | •                | •       |  |  |
| 2    | Input block                          | EX250-IE2        | M12, 4 inputs                         | •       | •                | •       |  |  |
|      |                                      | EX250-IE3        | M8, 4 inputs                          | •       | •                | •       |  |  |
| 3    | End plate assembly                   | EX250-EA1        | Standard                              | •       | •                | •       |  |  |
| 3    | Life piate assembly                  | EX250-EA2        | DIN rail mounting                     | •       | •                | _       |  |  |
|      |                                      | EX500-Q001       | DeviceNet ( +COM.)                    |         | _                | _       |  |  |
| 4    | SI unit                              | EX500-Q001-X1    | Remote I/O (+COM.)                    | •       | •                | •       |  |  |
| 4    | Si unit                              | EX500-Q101       | DeviceNet / PROFIBUS-DP (-COM.)       |         | _                |         |  |  |
|      |                                      | EX500-Q101-X1    | Remote I/O (–COM.)                    | •       | •                | •       |  |  |
| 5    | SI unit                              | EX240-SDN2       | DeviceNet (+COM.)                     | _       | _                | •       |  |  |
| 5    | Si unit                              | EX240-SPR1       | PROFIBUS-DP (-COM.)                   | _       | _                | •       |  |  |
| 6    | Input block                          | EX240-IE1        | M12, 8 inputs                         | _       | _                | •       |  |  |
| 7    | End cover assembly                   | EX240-EA2        | For manifold with input block         |         |                  | _       |  |  |
| ,    | End cover assembly                   | EX240-EA4        | For manifold without input block      | _       | _                | •       |  |  |
| 8    | SI unit                              | EX126D-SMJ1      | CC-Link (+COM.)                       | •       | •                | •       |  |  |
| 9    | Terminal plate                       | VVQC1000-74A-2   | For EX126 SI unit mounting            | •       | •                | •       |  |  |
| 10   | D-sub connector housing assembly     | VVQC1000-F25-1   | F Kit, 25-pin                         | •       | •                | •       |  |  |
| 11   | Flat ribbon cable housing assembly   | VVQC1000-P26-1   | P Kit, 26-pin                         | _       | _                | _       |  |  |
| 11   | Flat fibboli cable flousing assembly | VVQC1000-P20-1   | P Kit, 20-pin                         | •       | •                | •       |  |  |
| 12   | Terminal block box housing assembly  | VVQC1000-T0-1    | T Kit                                 | •       | •                | •       |  |  |
|      |                                      | VVQC1000-L25-0-1 | L Kit with 0.6m lead wire             |         |                  |         |  |  |
| 13   | Lead wire housing assembly           | VVQC1000-L25-1-1 | L Kit with 1.5m lead wire             | • •     |                  | •       |  |  |
|      |                                      | VVQC1000-L25-2-1 | L Kit with 3.0m lead wire             |         |                  |         |  |  |
| 14   | Multiple connector housing assembly  | VVQC1000-M26-1   | M Kit 26-pin                          | •       | •                | •       |  |  |
| 15   | Signal out blook                     | EX9-SC1-8        | Double wiring of 1st to 8th stations  | •       | •                | •       |  |  |
| 15   | Signal cut block                     | EX9-SC2-4        | Double wiring of 9th to 12th stations | •       | •                | •       |  |  |



#### U-side end plate assembly

®U-side end plate assembly part no.



| Suppl | y/Exh<br>entry |                    | C10<br>C12 |     |  |
|-------|----------------|--------------------|------------|-----|--|
|       | ,              |                    | ۱ ۱        | N9  |  |
| ()    | 1              | Cylinder port side |            | N11 |  |
|       | 2 Note)        | Branch type        | ] [        | N13 |  |
|       | Note) V        | QC2000 only        |            |     |  |

 Nil Centralized exhaust
R External pilot
S Direct exhaust outlet with built-in silencer

VQC4000 VVQC4000-2A-1


Thread type

Nil Rc
F G

NPT/NPTF

## Manifold block assembly

17 Manifold block assembly part no.




#### Port size

| Symbol | Port size                  | VQC1000 | VQC2000 | VQC4000 |
|--------|----------------------------|---------|---------|---------|
| C3     | for ø3.2 One-touch fitting | •       |         |         |
| C4     | for ø4 One-touch fitting   | •       | •       |         |
| C6     | for ø6                     | •       | •       |         |
| C8     | for ø8                     |         | •       | •       |
| C10    | for ø10                    |         |         | •       |
| C12    | for ø12                    |         |         | •       |
| N1     | for ø1/8"                  | •       |         |         |
| N3     | for ø5/32"                 | •       | •       |         |
| N7     | for ø1/4"                  | •       | •       | •       |
| N9     | for ø5/16"                 |         | •       | •       |
| N11    | for ø3/8"                  |         |         | •       |
| M5     | for M5 thread              | •       |         |         |
| 02     | Rc 1/4"                    |         |         | •       |
| 03     | Rc 3/8"                    |         |         | •       |
| В      | Rc 1/4" bottom ported      |         |         | •       |
| C0     | Without one-touch fitting  | •       | •       | •       |



## Series VQC1000: Base-Mounted Type/Plug-in Unit

#### How to order manifolds



#### 1 Stations

| 01 | 1 station |
|----|-----------|
| ÷  | ij        |

The maximum number of stations differs depending on the electrical entry. Refer to 3

#### (2) Cylinder pert size

| (2) ( | Cylinder port size                                 |
|-------|--|
| C3    | With ø3.2 One-touch fitting                        |
| C4    | With ø4 One-touch fitting                          |
| C6    | With ø6 One-touch fitting                          |
| M5    | M5 thread  |
| CM    | Mixed sizes and with port plug                     |
| L3    | Top ported elbow<br>Wtih ø3.2 One-touch fitting    |
| L4    | Top ported elbow<br>With ø4 One-touch fitting      |
| L6    | Top ported elbow<br>With ø6 One-touch fitting      |
| L5    | M5 thread  |
| В3    | Bottom ported elbow<br>With ø3.2 One-touch fitting |
| B4    | Bottom ported elbow<br>With ø4 One-touch fitting   |
| В6    | Bottom ported elbow<br>With ø6 One-touch fitting   |
| B5    | M5 thread  |
| LM    | Elbow port, mixed sizes                            |
|       |  |

Note 1) Indicate the size in the specification sheet in the case of CM and LM.

Note 2) Symbols for inch sizes are as follows:

#### <For One-touch fittings>

N1: ø1/8" N3: ø5/32 N7: ø1/4'

NM: Mixed

The top ported elbow is LN□ and the bottom ported elbow is BN ...

#### 3 Electrical entry/Cable length

|       |                 | ar ona yr oabio iongan                              |                  |  |  |  |
|-------|-----------------|---|------------------|--|--|--|
|       | D-side<br>entry | Kit, Cable length                                   | Stations Note 2) |  |  |  |
|       | FD0             | D-sub connector kit (25P) without cable             |                  |  |  |  |
| FKit  | FD1             | D-sub connector kit (25P) with 1.5m cable           | 1 40 10 (24)     |  |  |  |
|       | FD2             | D-sub connector kit (25P) with 3.0m cable           | 1 to 12 (24)     |  |  |  |
|       | FD3             | D-sub connector kit (25P) with 5.0m cable           | ]                |  |  |  |
|       | PD0             | Flat ribbon cable kit (26P) without cable           |                  |  |  |  |
|       | PD1             | Flat ribbon cable kit (26P) with 1.5m cable         | 1 to 12 (24)     |  |  |  |
| P Kit | PD2             | Flat ribbon cable kit (26P) with 3.0m cable         | 1 to 12 (24)     |  |  |  |
| а.    | PD3             | Flat ribbon cable kit (26P) with 5.0m cable         | ]                |  |  |  |
|       | PDC             | Flat ribbon cable kit (20P) without cable Note 1)   | 1 to 9 (18)      |  |  |  |
| Κ̈Ϊ   | TD0             | Terminal block box kit                              | 1 to 10 (20)     |  |  |  |
| 1     |                 |   | 1 to 10 (20)     |  |  |  |
| t     | LD0             | Lead wire kit (25 core) 0.6 m lead wire             |                  |  |  |  |
| Kit   | LD1             | Lead wire kit (25 core) 1.5 m lead wire             | 1 to 12 (24)     |  |  |  |
| 7     | LD2             | Lead wire kit (25 core) 3.0 m lead wire             | ]                |  |  |  |
|       | MD0             | Multiple connector kit (26P) without cable          |                  |  |  |  |
| 춫     | MD1             | Multiple connector kit (27P) with 1.5 m cable       | 1 +0 12 (24)     |  |  |  |
| Σ     | MD2             | Multiple connector kit (27P) with 3.0 m cable       | 1 to 12 (24)     |  |  |  |
|       | MD3             | Multiple connector kit (27P) with 5.0 m cable       | ]                |  |  |  |
|       |                 | Decentralized wiring serial kit (EX500)             |                  |  |  |  |
|       | SD0A            | Serial kit without SI unit                          | 1 to 8 (16)      |  |  |  |
|       | SDA1            | Serial kit for Remote I/O                           | 1 108 (16)       |  |  |  |
|       | SDA2            | Serial kit for DeviceNet/PROFIBUS-DP/CC-Link        | 1                |  |  |  |
|       |                 | Input/Output serial kit (EX250)                     |                  |  |  |  |
|       | SD0             | Serial kit without SI unit                          | 1                |  |  |  |
|       | SDQ             | Serial kit DeviceNet compatible                     | ]                |  |  |  |
| Α̈́   | SDN             | SDN Serial kit PROFIBUS-DP compatible               |                  |  |  |  |
| S     | SDV             | Serial kit CC-Link compatible                       | ]                |  |  |  |
|       | SDY             | Serial kit CANopen compatible                       | 1                |  |  |  |
|       | SDTA            | AS-i, 8 in/8 out, 31 slave modes, 2 power supply    | 1 to 4 (8)       |  |  |  |
|       | SDTB            | AS-i, 4 in/4 out, 31 slave modes, 2 power supply    | 1 to 2 (4)       |  |  |  |
|       | SDTC            | AS-i, 8 in/8 out, 31 slave modes, 1 power supply    | 1 to 4 (8)       |  |  |  |
|       | SDTD            | AS-i, 4 in/4 out, 31 slave modes, 1 power supply    | 1 to 2 (4)       |  |  |  |
|       |                 | Output serial transmission kit (EX126)              | 1 to 9 (10)      |  |  |  |
|       | SDVB            | Serial kit CC-Link compatible                       | 1 to 8 (16)      |  |  |  |
| Note  | 1) P Kit: Ord   | der the cable assembly separately for the type 20P. | •                |  |  |  |

Note 2) Numbers inside ( ) indicate the maximum number of solenoids for mixed single and double wiring. The maximum number of stations is determined by the total number of solenoids. In the case of mixed wiring, use the option symbol "-K".

#### (4) SI unit COM

|             | © 0. mm 00m |          |           |             |         |      |         |           |             |         |            |         |
|-------------|-------------|----------|-----------|-------------|---------|------|---------|-----------|-------------|---------|------------|---------|
| SI unit COM |             | :- 0014  |           | EX250       |         |      |         | EX500     |             |         |            | EX126   |
|             | OI UII      | IL COIVI | DeviceNet | PROFIBUS-DP | CC-Link | AS-i | CANopen | DeviceNet | PROFIBUS-DP | CC-Link | Remote I/O | CC-Link |
|             | Nil         | +COM     | _         | _           | 0       | —    | _       | 0         | 0           | 0       | 0          | 0       |
| ſ           | N           | -COM     | 0         | 0           | _       | 0    | 0       | 0         | 0           | 0       | 0          | _       |

Note) Leave the box blank for the SI unit COM without SI unit (SD0)

#### (5) Input block (Fill out for I/O unit only)

| Nil | Without SI unit/input block (SD0) |  |  |  |
|-----|-----------------------------------|--|--|--|
| 0   | Without input block               |  |  |  |
| 1   | With 1 input block                |  |  |  |
|     |                                   |  |  |  |
| 8   | With 8 input blocks               |  |  |  |

#### **6** Input block type (Fill out for I/O unit only)

| Nil | Without input block   |
|-----|-----------------------|
| 1   | M12, 2 inputs         |
| 2   | M12, 4 inputs         |
| 3   | M8, 4 inputs (3 pins) |

#### (7) Input block COM. (Fill out for I/O unit only)

| Nil | PNP (+) or without SI unit/input block |
|-----|--|
| N   | NPN (–)                                |

#### 9 Options

| Nil | None   |  |  |  |  |  |  |
|-----|--|--|--|--|--|--|--|
| В   | All stations with back pressure check valve Note 1)              |  |  |  |  |  |  |
| D   | With DIN rail (rail length: standard)                            |  |  |  |  |  |  |
| D□  | With DIN rail (rail length: special) Note 2)                     |  |  |  |  |  |  |
| K   | Special wiring specifications Note 3) (except for double wiring) |  |  |  |  |  |  |
| N   | With name plate  |  |  |  |  |  |  |
| R   | External pilot Note 4)   |  |  |  |  |  |  |
| S   | Direct exhaust with built-in silencer Note 5)                    |  |  |  |  |  |  |

When specifying more than one option, enter symbols in alphabetical order. Example: -BRS

Note 1) When using the back pressure check valve for the necessary stations only, enter the back pressure check valve part no. and indicate the number of manifold stations in the specification sheet.

Note 2) Erc, special DIN rail length indicate "DD"

Note 2) For special DIN rail length, indicate "D□." (Enter the number of stations inside □). Example: -D08

In this case, stations will be mounted on a DIN rail for 8 stations regardless of the actual number of manifold stations.

The specified number of stations must be larger than the number of stations on the manifold.


Indicate "-D0" for the option without DIN rail.

Note 3) Be sure to indicate the wiring specifications in the specification sheet.

Note 4) For external pilot option, "-R", indicate the external pilot specification "R" for the applicable valves as well.

Note 5) The built-in silencer type does not satisfy the IP67 standard.

#### How to order applicable valves



#### (A) Type of actuation

| 2-position single               |
|---------------------------------|
| 2-position double               |
| 3-position closed centre        |
| 3-position exhaust centre       |
| 3-position pressure centre      |
| Dual 3-port valve (N.C. + N.C.) |
| Dual 3-port valve (N.O. + N.O.) |
| Dual 3-port valve (N.C. + N.O.) |
|                                 |

Note) Available for the rubber seal type only.

#### (B) Seal type

| O |             |  |  |  |  |  |  |
|---|-------------|--|--|--|--|--|--|
| 0 | Metal seal  |  |  |  |  |  |  |
| 1 | Rubber seal |  |  |  |  |  |  |

#### © Function

| Nil       | Standard type (1W)         |  |  |  |  |  |
|-----------|----------------------------|--|--|--|--|--|
| K Note 1) | High voltage type (1.0MPa) |  |  |  |  |  |
| N         | Negative COM.              |  |  |  |  |  |
| R Note 2) | External pilot             |  |  |  |  |  |
| Υ         | Low wattage type (0.5W)    |  |  |  |  |  |

\* When specifying more than one option, enter symbols in alphabetical order.

Note 1) Available for the metal seal type only. Note 2) Not applicable to dual 3-port valve.


#### (D) Coil voltage

|       | Jon Tonago                  |
|-------|-----------------------------|
| 5     | 24VDC Note)                 |
| 6     | 12VDC                       |
| Note) | S kit is only available for |

**E** Light/Surge voltage

# suppressor

| Nil     | With                     |
|---------|--------------------------|
| Е       | Without Note)            |
| Note) N | Not applicable to S Kit. |



Stations are numbered in ascending order from the D-side.

#### (F) Manual override

| $\underline{\smile}$ |                                       |
|----------------------|---------------------------------------|
| Nil                  | Non-locking push type (tool required) |
| В                    | Slotted locking type (tool required)  |
| С                    | Locking type (manual)                 |
| D                    | Slide locking type (manual)           |



# Series VQC1000/Plug-in Unit

| Mani  | fold Model   |                                   |                         |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  | Date: |                    | /                  | /                 |
|---|--|-----------------------------------|-------------------------|-----------------------|------------------|--------------|--------------------|--------------------|------------------|----------|-----------------|--------|--------------------|---------|------------|---|--------|--------|--------------------|---------|-----------------|-----------------|------------------|-------|--------------------|--------------------|-------------------|
| <f, l<="" td=""><td>, M, P, T kit&gt;</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>Cı</td><td>ustom</td><td>er na</td><td>me</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></f,>                             | , M, P, T kit>   |                                   |                         |                       |                  |              |                    |                    |                  |          |                 |        |                    | Cı      | ustom      | er na   | me     |        |                    |         |                 |                 |                  |       |                    |                    |                   |
| VV5   | GQC <u>1 1</u> -   |                                   |                         |                       | $\exists \Gamma$ |              | }                  |                    |                  |          | $-\Gamma$       |        | 7                  | Co      | ontact     | pers  | on     |        |                    |         |                 |                 |                  |       |                    |                    | $\neg$            |
|   |  |                                   |                         |                       | ے ر<br>Fil       | ll out       | ifor S             | Kit on             | lv               |          | _               |        | _                  | Sp      | ecific     | ation   | shee   | et no. |                    |         |                 |                 |                  |       |                    |                    |                   |
| <s ki<="" td=""><td>_</td><td></td><td>—,-</td><td></td><td>7</td><td></td><td><math>\vec{\neg}</math></td><td><b>-</b></td><td>Á</td><td></td><td>_</td><td></td><td>٦</td><td>Ρι</td><td>ırchas</td><td>se or</td><td>der no</td><td>D.</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></s> | _  |                                   | —,-                     |                       | 7                |              | $\vec{\neg}$       | <b>-</b>           | Á                |          | _               |        | ٦                  | Ρι      | ırchas     | se or   | der no | D.     |                    |         |                 |                 |                  |       |                    |                    |                   |
| VV  | 5QC <u>1</u>   |                                   |                         |                       | ⅃L               | IJL          | ⅃L                 |                    | ╧                |          |                 |        |                    | E       | quipm      | ent n   | ame    |        |                    |         |                 |                 |                  |       |                    |                    |                   |
|   | l l Bass   | e-Mounte                          | م ماريد                 | ا ا<br>ا ا            | Cit ty           | /pe          |                    |                    |                  |          |                 | • O    | ptio               | n       | <br>uantit |   |        |        |                    | Se      | et(s)           | Real            | uired o          | date  |                    |                    |                   |
|   |  | VQC1000                           |                         | J-111                 |                  |              |                    |                    |                  |          |                 |        |                    |         |            | <u>,                                     </u> |        |        |                    |         | - (-/           |                 |                  |       |                    |                    |                   |
| Snec  | ifications   |                                   | <b>←</b> [г             | D-sic                 | le               |              |                    |                    |                  |          |                 |        | 1: 4 -             |         | :          |   |        | 41     | - 110              | \II     |                 |                 |                  |       | U-                 | side               | <b>→</b>          |
|   |  | Sta                               | ations                  | 1                     | 2                | 3            | 4                  | 5                  | 6                | 7        | 8               | * 1110 | licate             | 11      | 12         | _   |        | 15     | 16                 |         | 18              | 19              | 20               | 21    | 22                 | 23                 | 24                |
| Descrip   | otion/Model<br>Single  | (4)( <u>9</u> )                   | <u></u>                 |                       |                  |              |                    |                    |                  | <u> </u> |                 |        | 10                 |         |            | 10  |        |        | 10                 | .,      | 10              | 10              | 20               |       |                    |                    |                   |
|   | Double   | (R1)(P)((A)(B)                    | ***<br>***<br>***       |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
|   | Closed centre  | (A)(B)<br>11<br>11<br>(R1)(P)(R2) | ĪM                      |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
| Valves  | Exhaust centre   | (A)(B)                            |                         |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
| Va  | Pressure centre  | (R1)(P)(R2)                       |                         |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
|   | Dual 3-port valve<br>(A)   | (A) (B)                           | R <sub>2)</sub><br>N.C. |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
|   | Dual 3-port valve (B)  | (A) (B)                           | 3<br>R2)<br>N.O.        |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
|   | Dual 3-port valve<br>(C)<br>Blanking plate   | (R1) 1 (N.C. (P)                  | R2)<br>N.O.             |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
|   | VVQ1000-10A-1<br>Individual SUP space  | er                                |                         |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 | -               | -                |       |                    |                    | $\vdash$          |
|   | VVQ1000-P-1-C6<br>SUP shutoff position:  |                                   | sitions.                | <br> - <sub>T</sub> - | l.,.             | .l.,.        | .L. <sub>F</sub> . | .L. <sub>F</sub> . | l - <sub>1</sub> | . ,- :   | J. <sub>7</sub> | ٦- ٦-  | J <sub>-1-</sub> , | l . , . | l.,.       | l.,.  | ١-٢-   | ۱.,.   | L - <sub>[</sub> - | l_      | J. <sub>7</sub> | J. <sub>7</sub> | J <sub>- 1</sub> | l . , | l <sub>- T</sub> - | L _ <sub>T</sub> _ | Ĺ- <sub>[</sub> - |
| Options   | Individual EXH space<br>VVQ1000-R-1-C6<br>EXH shutoff position:<br>SUP block plate | er<br>i                           |                         | -   -                 | I.,.             |              | Ι                  | I .                |                  |          |                 |        | I                  | I - I - | Ι          | I -   -                                       | I.,.   | [      |                    |         |                 | <br>            |                  |       |                    | <br>               |                   |
| ō   | VVQ1000-16A<br>EXH shutoff position  | Note 1)                           |                         |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 | +               | +                |       |                    | _                  | +                 |
|   | When using EXH<br>VVQC1000-19A-  | block base                        | 1                       |                       |                  |              | $\perp$            |                    |                  |          |                 |        |                    |         |            | $\perp$                                       |        |        |                    |         | $\perp$         | $\perp$         | $\perp$          |       |                    |                    |                   |
|   | Port plug Note 2)  |                                   |                         | АВ                    | АВ               | A B          | AB                 | АВ                 | АВ               | АВ       | АВ              | АВ     | АВ                 | АВ      | АВ         | АВ  | АВ     | АВ     | АВ                 | АВ      | АВ              | АВ              | АВ               | АВ    | АВ                 | АВ                 | АВ                |
| ÷   | With ø3.2 (ø1/8")<br>One-touch fitting   | Side port                         | C3<br>(N1)              |                       |                  |              |                    |                    |                  |          |                 |        | •                  |         |            |   | •      | ,      |                    |         |                 |                 |                  | ·     |                    |                    |                   |
| S Note 3)<br>CM/LM/NM).   | With ø4 (ø5/32")<br>One-touch fitting  | Side port                         | C4<br>(N3)              |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
| ort sizes<br>xed sizes (  | With ø6 (ø1/4")<br>One-touch fitting   | Side port                         | C6<br>(N7)              |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
| Cylinder port sizes Note 3) Fill out in case of mixed sizes (CM/LM/NI   | M5 thread  | Side port                         | M5                      |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    |         |                 |                 | _                |       |                    |                    |                   |
| <b>Cyli</b><br>Fill out in  | Dual flow fixing   |                                   |                         |                       |                  |              |                    |                    | _                | <u> </u> |                 |        | _                  | _       |            | _   | _      |        |                    |         | _               |                 | <u></u>          |       |                    | <u></u>            | Щ                 |
|   | Dual flow fitting<br>VVQ1000-52A-Ca  |                                   |                         |                       |                  |              |                    |                    |                  |          |                 |        |                    |         |            |   |        |        |                    | $\perp$ |                 | $\perp$         |                  |       |                    | $\perp$            | Ш                 |
| Specifi   | al wiring <sup>Note 4)</sup><br>cations  | Single wi                         |                         |                       |                  |              |                    |                    |                  |          |                 | -      |                    |         |            |   |        |        |                    |         |                 | <del> </del>    | -                |       |                    |                    | $\vdash$          |
|   | ption/Model  | Double w                          |                         | _                     | -                |              |                    | -                  |                  | -        |                 | _      | 10                 | 44      | 10         | 10  | 1.4    | 15     | 10                 | 17      | 10              | 10              | 20               | 24    | 20                 | 22                 | 24                |
|   |  |                                   | ations                  | The                   | 2<br>D-sid       | 3<br>te of t | 4<br>the F         | 5<br>XH N          | 6<br>ock ir      | 7        | 8<br>EYH        | 9      | 10                 | 11      | 12<br>ked  | 13  | 14     | 15     | 16                 | 17      | 18              | 19              | 20               | 21    | 22                 | 23                 | 24                |
| Notes   | Note 1) Indicate the Note 2) When using Note 3) When more                          | ng port plug                      | s, circle               | por                   | ts to s          | speci        | fy.                |                    |                  |          |                 |        |                    |         |            | oove.   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |
| _   | Note 4) In case of   | single wirin<br>ny terminal:      | g or mi                 | xed v                 | wiring           | g, con       | necti              | ons to             | the              | conn     | ector           | termi  | nals s             | start 1 | rom t      | he A-   | side   | solen  | oid o              | fstati  | on 1            | and c           | ontin            | ue in | ordeı              | with               | out               |
| Anni  | icable valves  | and or                            | ation                   |                       |                  |              |                    |                    | – F              | or S     | MC              | use    | onl                | у –     |            |   |        |        |                    |         |                 |                 |                  |       |                    |                    |                   |

| Part no. | Qty. |
|----------|------|
|          |      |
|          |      |
|          |      |
|          |      |
|          |      |


| Part no. | Qty. |
|----------|------|
|          |      |
|          |      |
|          |      |
|          |      |
|          |      |

| Order no.        |  |
|------------------|--|
| Clerk (code no.) |  |
| Dept. code       |  |



## Series VQC2000: Base-Mounted Type/Plug-in Unit

#### How to order manifolds



#### 1 Stations

| 01 | 1 station |
|----|-----------|
| i  | :         |

The maximum number of stations differs depending on the electrical entry. Refer to 3

#### 2 Cylinder port size

| <u>⊘</u> ( | yiiilder port size                               |
|------------|--|
| C4         | With ø4 One-touch fitting                        |
| C6         | With ø6 One-touch fitting                        |
| C8         | With ø8 One-touch fitting                        |
| CM         | Mixed or with port plug                          |
| L4         | Top ported elbow<br>With ø4 One-touch fitting    |
| L6         | Top ported elbow<br>With ø6 One-touch fitting    |
| L8         | Top ported elbow<br>With ø8 One-touch fitting    |
| B4         | Bottom ported elbow<br>With ø4 One-touch fitting |
| В6         | Bottom ported elbow<br>With ø6 One-touch fitting |
| В8         | Bottom ported elbow<br>With ø8 One-touch fitting |
| LM         | Elbow port, mixed sizes                          |

Note 1) Indicate the size in the specification sheet in the case of CM and LM.

Note 2) Symbols for inch sizes are as follows

#### <For One-touch fittings>

N3: ø5/32"

N7: ø1/4"

N9: ø5/16'

NM: Mixed

The top ported elbow is LN□ and the bottom ported elbow is  $BN\square$ .

#### 3 Electrical entry/Cable length

| ·        |                 | ar ona y oabio longar                               |                  |
|----------|-----------------|---|------------------|
|          | D-side<br>entry | Kit, Cable length                                   | Stations Note 2) |
|          | FD0             | D-sub connector kit (25P) without cable             |                  |
| ¥        | FD1             | D-sub connector kit (25P) with 1.5m cable           | 1 40 10 (24)     |
| 표        | FD2             | D-sub connector kit (25P) with 3.0m cable           | 1 to 12 (24)     |
|          | FD3             | D-sub connector kit (25P) with 5.0m cable           |                  |
|          | PD0             | Flat ribbon cable kit (26P) without cable           |                  |
| Į.       | PD1             | Flat ribbon cable kit (26P) with 1.5m cable         | 1 40 10 (24)     |
| Ķ        | PD2             | Flat ribbon cable kit (26P) with 3.0m cable         | 1 to 12 (24)     |
| ۵        | PD3             | Flat ribbon cable kit (26P) with 5.0m cable         |                  |
|          | PDC             | Flat ribbon cable kit (20P) without cable Note 1)   | 1 to 9 (18)      |
| ž        | TD0             | Terminal block box kit                              | 4 += 40 (00)     |
| <u>_</u> |                 |   | 1 to 10 (20)     |
|          | LD0             | Lead wire kit (25 core) 0.6 m lead wire             |                  |
| ž        | LD1             | Lead wire kit (25 core) 1.5 m lead wire             | 1 to 12 (24)     |
| _        | LD2             | Lead wire kit (25 core) 3.0 m lead wire             |                  |
|          | MD0             | Multiple connector kit (26P) without cable          |                  |
| ž        | MD1             | Multiple connector kit (27P) with 1.5 m cable       | 1 to 12 (24)     |
| Ξ        | MD2             | Multiple connector kit (27P) with 3.0 m cable       | 1 10 12 (24)     |
|          | MD3             | Multiple connector kit (27P) with 5.0 m cable       |                  |
|          |                 | Decentralized wiring serial kit (EX500)             |                  |
|          | SD0A            | Serial kit without SI unit                          | 1 40 0 (16)      |
|          | SDA1            | Serial kit for Remote I/O                           | 1 to 8 (16)      |
|          | SDA2            | Serial kit for DeviceNet/PROFIBUS-DP/CC-Link        |                  |
|          |                 | Input/Output serial kit (EX250)                     |                  |
|          | SD0             | Serial kit without SI unit                          |                  |
|          | SDQ             | Serial kit DeviceNet compatible                     |                  |
| 춫        | SDN             | Serial kit PROFIBUS-DP compatible                   | 1 to 12 (24)     |
| S        | SDV             | Serial kit CC-Link compatible                       |                  |
|          | SDY             | Serial kit CANopen compatible                       | 1                |
|          | SDTA            | AS-i, 8 in/8 out, 31 slave modes, 2 power supply    | 1 to 4 (8)       |
|          | SDTB            | AS-i, 4 in/4 out, 31 slave modes, 2 power supply    | 1 to 2 (4)       |
|          | SDTC            | AS-i, 8 in/8 out, 31 slave modes, 1 power supply    | 1 to 4 (8)       |
|          | SDTD            | AS-i, 4 in/4 out, 31 slave modes, 1 power supply    | 1 to 2 (4)       |
|          |                 | Output serial transmission kit (EX126)              | 1 to 9 (16)      |
|          | SDVB            | Serial kit CC-Link compatible                       | 1 to 8 (16)      |
| Note     | 1) P Kit: Ord   | ler the cable assembly separately for the type 20P. |                  |

Note 2) Numbers inside ( ) indicate the maximum number of solenoids for mixed single and double wiring. The maximum number of stations is determined by the total number of solenoids. In the case of mixed wiring, use the option symbol "-K".

#### (4) SI unit COM.

| SI unit COM |      |           | EX250       |         |      |         |           | EX          | 500     |            | EX126   |
|-------------|------|-----------|-------------|---------|------|---------|-----------|-------------|---------|------------|---------|
|             |      | DeviceNet | PROFIBUS-DP | CC-Link | AS-i | CANopen | DeviceNet | PROFIBUS-DP | CC-Link | Remote I/O | CC-Link |
| Nil         | +COM | _         | _           | 0       | _    | _       | 0         | 0           | 0       | 0          | 0       |
| N           | -COM | 0         | 0           | _       | 0    | 0       | 0         | 0           | 0       | 0          | _       |

Note) Leave the box blank for the SI unit COM without SI unit (SD0).

#### **5** Input block (Fill out for I/O unit only)

| Nil | Without SI unit/input block (SD0) |  |
|-----|-----------------------------------|--|
| 0   | Without input block               |  |
| 1   | With 1 input block                |  |
|     |                                   |  |
| 8   | With 8 input blocks               |  |

#### 6 Input block type (Fill out for I/O unit only)

| Nil | Without input block   |
|-----|-----------------------|
| 1   | M12, 2 inputs         |
| 2   | M12, 4 inputs         |
| 3   | M8, 4 inputs (3 pins) |

#### (7) Input block COM. (Fill out for I/O unit only)

| Nil | PNP (+) or without SI unit/input block |
|-----|--|
| N   | NPN (-)                                |

#### (9) Options

|        | •  |
|--------|--|
| Nil    | None   |
| В      | All stations with back pressure check valve Note 1)              |
| D      | With DIN rail (rail length: standard)                            |
| D□     | With DIN rail (rail length: special) Note 2)                     |
| K      | Special wiring specifications Note 3) (except for double wiring) |
| N      | With name plate  |
| R      | External pilot Note 4)   |
| S      | Direct exhaust with built-in silencer Note 5)                    |
| Т      | Branched P and R ports on U side Note 6)                         |
| * When | enecifying more than one option, enter symbols in                |

When specifying more than one option, enter symbols in alphabetical order. Example: BRS
Note 1) When using the back pressure check valve for the necessary stations only, enter the back pressure check valve part no. and indicate the number of manifold stations in the specification sheet.
Note 2) For special DIN rail length, indicate "D□." (Enter the number of stations inside □.)
Example: -Do8
In this case, stations will be mounted on a DIN rail for 8 stations regardless of the actual number of manifold stations.
The specified number of stations must be larger than the number of stations on the manifold.

\*\*The specified number of stations must be larger than the number of stations on the manifold.\*\*

\*\*The specified number of stations on the manifold.\*\*

than the number of stations on the manifold.
Indicate "-D0" for the option without DIN rail.
Note 3) Be sure to indicate the wiring specifications in the


specification sheet.

Note 4) For external pilot option, "-R", indicate the external pilot specification "R" for the applicable valves as

Note 5) The built-in silencer type does not satisfy the IP67 standard.

Note 6) The SUP and EXH ports on U side are branched (toward the cylinder port and coil) with ø12 one-touch fittings for connection.

#### 2 How to order applicable valves



#### A Type of actuation

| 1       | 2-position single               |
|---------|---------------------------------|
| 2       | 2-position double               |
| 3       | 3-position closed centre        |
| 4       | 3-position exhaust centre       |
| 5       | 3-position pressure centre      |
| A Note) | Dual 3-port valve (N.C. + N.C.) |
| B Note) | Dual 3-port valve (N.O. + N.O.) |
| C Note) | Dual 3-port valve (N.C. + N.O.) |

Note) Available for the rubber seal type only.

#### **B** Seal type

| 0 | Metal seal  |
|---|-------------|
| 1 | Rubber seal |

#### © Function

| · ui                   | © i dilotion               |  |  |  |  |
|------------------------|----------------------------|--|--|--|--|
| Nil Standard type (1W) |                            |  |  |  |  |
| K Note 1)              | High voltage type (1.0MPa) |  |  |  |  |
| N                      | Negative COM.              |  |  |  |  |
| R Note 2)              | External pilot             |  |  |  |  |
| Υ                      | Low wattage type (0.5W)    |  |  |  |  |

\* When specifying more than one option, enter symbols in alphabetical order. Note 1) Available for the metal seal type only. Note 2) Not applicable to Dual 3-port valve

#### (D) Coil voltage


| <u> </u> | Jon voltage |
|----------|-------------|
| 5        | 24VDC Note) |
| 6        | 12VDC       |

Note) S kit is only available for 24VDC

#### (E) Light/Surge voltage suppressor

| Nil With |               |
|----------|---------------|
| Е        | Without Note) |
|          |               |

Note) Not applicable to S Kit.



D-side Stations---1---2---3----4---5----6---7---8----n U-side


Stations are numbered in ascending order

#### (F) Manual override

| · manaar overnae |                                       |  |  |  |  |  |  |  |
|------------------|---------------------------------------|--|--|--|--|--|--|--|
|                  | Non-locking push type (tool required) |  |  |  |  |  |  |  |
| В                | Slotted locking type (tool required)  |  |  |  |  |  |  |  |
| С                | Locking type (manual)                 |  |  |  |  |  |  |  |
| D                | Slide locking type (manual)           |  |  |  |  |  |  |  |



## Series VQC2000/Plug-in Unit



#### Applicable valves and options

|  | Part no. | Qty. |
|--|----------|------|
|  |          |      |
|  |          |      |
|  |          |      |
|  |          |      |
|  |          |      |

| Part no. | Qty. |
|----------|------|
|          |      |
|          |      |
|          |      |
|          |      |
|          |      |


For SMC use only —--

| Order no.        |   |
|------------------|---|
| Clerk (code no.) |   |
| Dept. code       | - |



## Series VQC4000: Base-Mounted Type/Plug-in Unit

#### How to order manifolds



#### (1) Stations

| 01 | 1 station |
|----|-----------|
| :  | i         |

The maximum number of stations differs depending on the electrical entry. Refer to 3

#### 2 Cylinder port size

| C8  | With ø8 One-touch fitting  |
|-----|----------------------------|
| C10 | With ø10 One-touch fitting |
| C12 | With ø12 One-touch fitting |
| 02  | Rc 1/4                     |
| 03  | Rc 3/8                     |
| В   | Bottom ported Rc 1/4       |
| СМ  | Mixed                      |

Note 1) Indicate the size in the specification order sheet in the case of CM

Note 2) Symbols for inch sizes are as follows

#### <For One-touch fittings>

N7: ø1/4" N9: ø5/16" N11: ø3/8" NM: Mixed

#### <For threads> P, R, A, B port

| V | / V D U | C41- | UOU. | <b>5</b> |   |
|---|---------|------|------|----------|---|
|   |         |      |      |          | _ |
|   |         |      |      |          |   |
|   |         |      |      |          |   |

Cylinder port 4 Thread type

| Nil | Rc       |
|-----|----------|
| F   | G        |
| Т   | NPT/NPTF |

Note) P and R ports use the same type of threads.

#### 3 Electrical entry

|       | D-side<br>entry | Kit, Cable length                                   | Stations Note 2) |  |  |  |  |  |
|-------|-----------------|---|------------------|--|--|--|--|--|
|       | FD0             | D-sub connector kit (25P) without cable             |                  |  |  |  |  |  |
| 출     | FD1             | D-sub connector kit (25P) with 1.5m cable           | 1 to 12 (24)     |  |  |  |  |  |
| 正     | FD2             | D-sub connector kit (25P) with 3.0m cable           | 1 10 12 (24)     |  |  |  |  |  |
|       | FD3             | D-sub connector kit (25P) with 5.0m cable           |                  |  |  |  |  |  |
|       | PD0             | Flat ribbon cable kit (26P) without cable           |                  |  |  |  |  |  |
| ٠.    | PD1             | Flat ribbon cable kit (26P) with 1.5m cable         | 1 to 12 (24)     |  |  |  |  |  |
| ķ     | PD2             | Flat ribbon cable kit (26P) with 3.0m cable         | 1 10 12 (24)     |  |  |  |  |  |
| ۵     | PD3             | Flat ribbon cable kit (26P) with 5.0m cable         |                  |  |  |  |  |  |
|       | PDC             | Flat ribbon cable kit (20P) without cable Note 1)   | 1 to 9 (18)      |  |  |  |  |  |
| ž     | TD0             | Terminal block box kit                              | 1 to 10 (20)     |  |  |  |  |  |
| F     |                 |   | 1 10 10 (20)     |  |  |  |  |  |
| يب    | LD0             | Lead wire kit (25 core) 0.6m lead wire              |                  |  |  |  |  |  |
| L Kit | LD1             | Lead wire kit (25 core) 1.5m lead wire              | 1 to 12 (24)     |  |  |  |  |  |
| _     | LD2             | Lead wire kit (25 core) 3.0m lead wire              |                  |  |  |  |  |  |
|       | MD0             | Multiple connector kit (26P) without cable          |                  |  |  |  |  |  |
| 춫     | MD1             | Multiple connector kit (27P) with 1.5m cable        | 1 to 12 (24)     |  |  |  |  |  |
| Σ     | MD2             | MD2 Multiple connector kit (27P) with 3.0m cable    |                  |  |  |  |  |  |
|       | MD3             | Multiple connector kit (27P) with 5.0m cable        |                  |  |  |  |  |  |
|       |                 | Decentralized wiring serial kit (EX500)             |                  |  |  |  |  |  |
|       | SD0A            | Serial kit without SI unit                          |                  |  |  |  |  |  |
|       | SDA1            | Serial kit for Remote I/O                           | 1 to 8 (16)      |  |  |  |  |  |
|       | SDA2            | Serial kit for DeviceNet/PROFIBUS-DP/CC-Link        |                  |  |  |  |  |  |
|       |                 |   |                  |  |  |  |  |  |
|       | SD0             | Serial kit without SI unit                          | ]                |  |  |  |  |  |
|       | SDQ             | Serial kit DeviceNet compatible                     |                  |  |  |  |  |  |
|       | SDN             | Serial kit PROFIBUS-DP compatible                   | 1 to 12 (24)     |  |  |  |  |  |
|       | SDV             | Serial kit CC-Link compatible                       |                  |  |  |  |  |  |
|       | SDY             | SDY Serial kit CANopen compatible                   |                  |  |  |  |  |  |
| ž     | In              | put/Output serial transmission kit (EX240)          |                  |  |  |  |  |  |
| S     | SD0W            | Serial kit without SI unit                          |                  |  |  |  |  |  |
|       | SDQW            | Serial kit DeviceNet compatible                     | 1 to 12 (16)     |  |  |  |  |  |
|       | SDNW            | Serial kit PROFIBUS-DP compatible                   | 1 10 12 (10)     |  |  |  |  |  |
|       | SDVW            | Serial kit CC-Link compatible                       |                  |  |  |  |  |  |
|       | SDTA            | AS-i, 8 in/8 out, 31 slave modes, 2 power supply    | 1 to 4 (8)       |  |  |  |  |  |
|       | SDTB            | AS-i, 4 in/4 out, 31 slave modes, 2 power supply    | 1 to 2 (4)       |  |  |  |  |  |
|       | SDTC            | AS-i, 8 in/8 out, 31 slave modes, 1 power supply    | 1 to 4 (8)       |  |  |  |  |  |
|       | SDTD            | AS-i, 4 in/4 out, 31 slave modes, 1 power supply    | 1 to 2 (4)       |  |  |  |  |  |
|       |                 | Output serial transmission kit (EX126)              |                  |  |  |  |  |  |
|       | SDVB            | Serial kit CC-Link compatible                       | 1 to 8 (16)      |  |  |  |  |  |
|       |                 | der the cable assembly separately for the type 20P. | ed single and    |  |  |  |  |  |

Note 2) Numbers inside () indicate the maximum number of solenoids for mixed single and double wiring. The maximum number of stations is determined by the total number of solenoids. In the case of mixed wiring, use the option symbol "-K".

| G of drift com. |             |      |                     |             |           |             |         |      |         |           |             |         |            |         |
|-----------------|-------------|------|---------------------|-------------|-----------|-------------|---------|------|---------|-----------|-------------|---------|------------|---------|
| [               | SI unit COM |      | eit COM EX240 EX250 |             |           |             | EX500   |      |         |           | EX126       |         |            |         |
| ľ               |             |      | DeviceNet           | PROFIBUS-DP | DeviceNet | PROFIBUS-DP | CC-LINK | AS-i | CANopen | DeviceNet | PROFIBUS-DP | CC-LINK | Remote I/O | CC-LINK |
| į               | Nil         | +COM | 0                   | _           | _         | _           | 0       | -    | _       | 0         | 0           | 0       | 0          | 0       |
| ſ               | N           | -COM | 0                   | 0           | 0         | 0           |         | 0    | 0       | 0         | 0           | 0       | 0          | _       |

Note) Leave the box blank for the SI unit COM. without SI unit (SD0)

#### 2 How to order applicable valves

#### VQC 4 1 0 0 Y-5 EB Series VQC4000

#### (A) Type of actuation

|                              | 1 2-position single         |  |  |  |  |  |
|------------------------------|-----------------------------|--|--|--|--|--|
| 2 2-position double          |                             |  |  |  |  |  |
| 3 3-position closed centre   |                             |  |  |  |  |  |
|                              | 4 3-position exhaust centre |  |  |  |  |  |
| 5 3-position pressure centre |                             |  |  |  |  |  |
|                              | 6 3-position perfect        |  |  |  |  |  |

#### (D) Coil voltage

| B con ronage |             |  |  |  |  |  |
|--------------|-------------|--|--|--|--|--|
| 5            | 24VDC Note) |  |  |  |  |  |
| 6            | 12VDC       |  |  |  |  |  |

Note) S kit is only available for 24VDC.

#### (B) Seal type

| $\sim$ | 7.          |  |  |  |  |  |  |
|--------|-------------|--|--|--|--|--|--|
| 0      | Metal seal  |  |  |  |  |  |  |
| 1      | Rubber seal |  |  |  |  |  |  |

#### **E**Light/Surge voltage suppressor

## © Function

| Nil | Standard type (1W)      |
|-----|-------------------------|
| R   | External pilot          |
| Υ   | Low wattage type (0.5W) |

\* When specifying more than one option, enter symbols in alphabetical order.

#### With Without light, with surge voltage supressor

#### (F) Manual override

| <u> </u> |                                       |  |  |  |  |  |  |
|----------|---------------------------------------|--|--|--|--|--|--|
| Nil      | Non-locking push type (tool required) |  |  |  |  |  |  |
| В        | Slotted locking type (tool required)  |  |  |  |  |  |  |

#### (5) Input block (Fill out for I/O unit only)

| Nil | Without SI unit/input block [SD0(W)] |
|-----|--------------------------------------|
| 0   | Without input block                  |
| 1   | With 1 input block                   |
|     |                                      |
| 8   | With 8 input blocks                  |
|     |                                      |

Note) Max. 4 for EX240 and max 8 for EX250.

#### 6 Input block type (Fill out for I/O unit only)

|     | · · · · · · · · · · · · · · · · · · · |
|-----|---------------------------------------|
| Nil | Without input block                   |
| 1   | M12, 8 inputs (EX240)                 |
| 2   | M12, 2 inputs (EX250)                 |
| 3   | M12, 4 inputs (EX250)                 |
| 4   | M8. 4 inputs (EX250)                  |

#### (7) Input block COM. (Fill out for I/O unit only)


|     | (* •                                   |  |  |  |  |  |  |  |  |
|-----|--|--|--|--|--|--|--|--|--|
| Nil | PNP (+) or without SI unit/input block |  |  |  |  |  |  |  |  |
| N   | NPN (–)                                |  |  |  |  |  |  |  |  |

#### 9 Options

| N | lil      | None   |
|---|----------|--|
| ŀ | <b>(</b> | Special wiring specifications Note 1) (except for double wiring) |
| 1 | 1        | With name plate Note 2) (available for T Kit only)               |

\* When specifying more than one option, enter symbols in alphabetical order. Example: -KN Note 1) Be sure to indicate the wiring specifications in the specification order sheet.

Note 2) The mounting position of the name plate is on the top face of the cover for the terminal block box.




\* Stations are numbered in ascending order from the D-side.



# Series VQC4000/Plug-in Unit

**Manifold Model** 



|                         |        | Date: /       | / |  |
|-------------------------|--------|---------------|---|--|
| Customer name           |        |               |   |  |
| Contact person          |        |               |   |  |
| Specification sheet no. |        |               |   |  |
| Purchase order no.      |        |               |   |  |
| Equipment name          |        |               |   |  |
| Quantity                | set(s) | Required date |   |  |

| pec   | cifications   | ←   | D-sid    | е        |   |   |   |          |          | *    | Indic    | ate i | requi    | ired s | static   | ons v | vith a   | "O" |    |          |          |     |          | U-       | side     | – اِدِ |
|---|---|---|----------|----------|---|---|---|----------|----------|------|----------|-------|----------|--------|----------|-------|----------|-----|----|----------|----------|-----|----------|----------|----------|--------|
| escrip  | otion/Model   | Stations  | 3 1      | 2        | 3 | 4 | 5 | 6        | 7        | 8    | 9        | 10    | 11       | 12     | 13       | 14    | 15       | 16  | 17 | 18       | 19       | 20  | 21       | 22       | 23       | 2      |
|   | Single  | (A)(B)<br>(A)(B)<br>(B1)(P)(R2)   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
|   | Double  | (A) (B)<br>4 2<br>5 1 3<br>(R1) (P) (R2)  |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | Ī      |
| Valves  | Closed centre   | (A)(B)<br>111<br>111<br>(R1)(P)(R2)   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
| Na  | Exhaust centre  | (A)(B)<br>4 2<br>T 1 3<br>(R1)(P)(R2)   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
|   | Pressure centre   | (A)(B)<br>T T T T T T T T T T T T T T T T T T T   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
|   | Perfect   | $\bigwedge_{\substack{4 \\ 4 \\ 2 \\ 7 \\ 7 \\ (R_1)(P)(R_2)}} \bigwedge_{4 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ $ |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
|   | Blanking plate<br>VVQ4000-10A-1                                   |   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | I      |
|   | Individual SUP sp<br>VVQ4000-P-1-02/                              | acer<br>/03   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | İ      |
|   | Individual EXH sp<br>VVQ4000-P-1-02/                              | acer<br>/03   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
|   | Throttle valve spa<br>VVQ4000-20A-1                               | cer   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
| SUC   | Perfect spacer with residual pressure release valve VVQ4000-25A-1 |   | е        |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
| Options   | Interface regulator<br>ARBQ4000-00-A-                             | r (A regulator)   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | İ      |
|   | Interface regulator (B regulator)<br>ARBQ4000-00-B-1              |   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
|   | Interface regulator ARBQ4000-00-P-                                |   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | 1      |
|   |   | P   | 1        | <u> </u> | Ļ | - | Ļ | <u> </u> | <u> </u> | Ļ    | <u> </u> | -     | <u> </u> | 1      | <u> </u> | Ļ     | <u> </u> |     |    | <u> </u> | <u> </u> | -   | _        | <u> </u> | <u> </u> | 1      |
|   | SUP/EXH block pl<br>VVQ4000-16A                                   | IX.   |          |          | 1 |   |   |          |          | -    |          |       | -        |        |          | 1     |          |     |    | 1        | -        |     | 1        |          |          | _      |
| —<br>(g   | Rc 1/4  | 02  | <u> </u> | T        | Ľ | l | Ė |          |          | <br> |          | -     |          |        | <u> </u> | Ė     | İ        |     |    | Ė        |          | - 1 | <u> </u> |          |          | T      |
| SM/LM/N   | Rc 3/8  | 03  |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | t      |
| d sizes ((  | With Ø8 (Ø1/4")<br>One-touch fitting                              | C8<br>(N7)  |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | 1      |
| Cylinder port sizes at in case of mixed sizes (CM/LM/NM). | With ø10 (ø5/16") C10<br>One-touch fitting (N9)                   |   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | Ī      |
|   | With ø12 (ø3/8") C10<br>One-touch fitting (N11                    |   | )        |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
| Fill out  | Bottom ported Ro  | : 1/4   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          |        |
| Spec  | cial wiring Note 1)   | Single wiring   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | 1      |
|   | ifications  | Double wiring   |          |          |   |   |   |          |          |      |          |       |          |        |          |       |          |     |    |          |          |     |          |          |          | Ţ      |
| scrip   | otion/Model   | Stations  | 1        | 2        | 3 | 4 | 5 | 6        | 7        | 8    | 9        | 10    | 11       | 12     | 13       | 14    | 15       | 16  | 17 | 18       | 19       | 20  | 21       | 22       | 23       |        |

#### Applicable valves and options

skipping any terminals.

| Part no. | Qty. |
|----------|------|
|          |      |
|          |      |
|          |      |
|          |      |
|          |      |

| Part no. | Qty. |
|----------|------|
|          |      |
|          |      |
|          |      |
|          |      |
|          |      |

- For SMC use only —---

| Order no.        |  |
|------------------|--|
| Clerk (code no.) |  |
| Dept. code       |  |



# Flow Characteristics of Solenoid Valve

# (How to Express Flow Characteristics)

#### 1. Express of Flow Characteristics

Table 1 shows the applicable International designation of flow characteristics in the specification section of a solenoid valve or any other types of equipment.

Table 1 Designation of flow characteristics

| Equipment               | Designation based on international standards | Other designation | Applicable standards  |  |
|-------------------------|--|-------------------|---|--|
| Pneumatics<br>equipment | C, b   |                   | ISO 6358: 1989<br>JIS B 8390: 2000                                |  |
|                         |  | S                 | JIS B 8390: 2000<br>Equipment: JIS B 8373, 8374, 8375, 8379, 8381 |  |
|                         |  | Cv                | ANSI/(NFPA)T3.21.3: 1990  |  |

#### 2. Pneumatic Equipment

2-1 Calculating flow rate according to International Standards

(1)Flow rate calculation formula

The flow rate calculation formula is defined as follows:

If 
$$\frac{P_2+0.1}{P_1+0.1} \le b$$
, a choke flow results.

Q=600XC(P<sub>1</sub>+0.1) 
$$\sqrt{\frac{293}{273+t}}$$

If 
$$\frac{P_2+0.1}{P_1+0.1}$$
 > b, a subsonic flow results.

Q=600XC (P1+0.1) 
$$\sqrt{1-\left[\begin{array}{c} \frac{P2+0.1}{P1+0.1} \\ \hline 1-b \end{array}\right]^2} \sqrt{\frac{293}{273+t}}$$

#### Q: Air flow rate [dm3/min(ANR)].

The dm³ (cubic decimeter) in the SI system may be expressed by L(liter). 1dm³=1L. Standard condition: Air under condition temperature 20°C, absolute pressure 0.1MPa (=100kPa=1bar), relative humidity 65%.

C: Sonic conductance [dm³/(s•bar)]

b: Critical pressure ratio [-]

P<sub>1</sub>: Upstream pressure [MPa]

P2: Downstream pressure [MPa]

t: Temperature [°C]

Note) The formula for subsonic flow is that of an elliptic approximate curve.

Figure 1 is the flow characteristic diagram. For more information, please see Energy Saving Programs by SMC.




Figure 1 Flow rate characteristic diagram

#### (2) Test method

Pipe the test equipment to the test circuit shown in Figure 2. Keep the upstream pressure at a certain constant level above 0.3MPa. First measure the maximum flow rate in saturation. Then, measure the flow rate, upstream pressure and downstream pressure each at 80%, 60%, 40% and 20% points of the flow rate. Calculate the sonic conductance C from the maximum flow rate. Also, substitute other data for variables in the formula for sobsonic flow and obtain the critical pressure rate b by averaging the critical pressure rates at those points.

Pressure gauge or pressure transducer




Figure 2 Test circuit of ISO 6358 and JIS B 8390

#### 2.2 Effective sectional area S

(1) Calculation with subsonic conductance C:

S = 5.0 X C

#### 2) Test method

Pipe the test equipment to the test circuit shown in Figure 3. Fill the air tank with compressed air and keep the pressure at a constant level above 0.6MPa. Then discharge the air until the pressure in the tank drops to 0.25MPa. Measure the time required to discharge the air and the residual pressure in the air tank after leaving it until the pressure becomes stable in order to calculate the effective sectional area S by the following formula. Select the capacity of the air tank according to the effective sectional area of the test equipment.

$$S = 12.1 \frac{V}{t} log_{10} \left( \frac{Ps + 0.1}{P + 0.1} \right) \sqrt{\frac{293}{T}}$$

S: Effective sectional area [mm²]

V: Air tank capacity [dm3]

t : Discharge time [s]

Ps: Pressure in the air tank before discharge [MPa]

P: Residual pressure in the air tank after discharge [MPa]

T: Temperature in the air tank before discharge [K]




Figure 3. Test circuit of JIS B 8390

#### 2.3 Flow coefficient Cv factor

The flow coefficient Cv factor is defined with the following formula in the U.S. standard ANSI/(NFPA)T3.21.3: 1990: Pneumatic fluid power - Flow rating test procedure and reporting method - For fixed orifice components

$$Cv = \frac{Q}{114.5 \sqrt{\frac{\triangle P (P_2 + P_a)}{T_1}}}$$

 $\triangle P$ : Pressure drop between static pressure output ports [bar]

P<sub>1</sub>: Pressure at ustream output port [bar gauge]

 $P_2$ : Pressure at downstream output port [bar gauge]:  $P_2$ = $P_1$ - $\triangle P$ 

Q : Flow rate [dm<sup>3</sup>/s standard atmosphere]

Pa: Atmospheric pressure [bar absolute]

T<sub>1</sub>: Upstream absolute temperature [K]

Test conditions are  $P_1+P_a=6.5\pm0.2$  bar absolute,  $T_1=297\pm5K$ ,  $0.07bar \le \triangle P \le 0.14$  bar.

This concept is similar to the effective area in ISO 6358, which is described to be applicable only if the pressure drop is so small compared with the upstream pressure that air compression is negligible.





# Series VQC Safety Instructions

These safety instructions are intended to prevent a hazardous situation and/or equipment damage. These instructions indicate the level of potential hazard by a label of **"Caution"**, **"Warning"** or **"Danger"**. To ensure safety, be sure to observe ISO 4414 Note 1), JIS B 8370 Note 2) and other safety practices.

**Caution:** Operator error could result in injury or equipment damage.

**Warning:** Operator error could result in serious injury or loss of life.

⚠ Danger: In extreme conditions, there is a possible result of serious injury or loss of life.

Note 1) ISO4414: Pneumatic fluid power — General rules relating to systems.

Note 2) JIS B 8370: General rules for pneumatic equipment

# **⚠** Warning

1. The compatibility of pneumatic equipment is the responsibility of the person who designs the pneumatic system or decides its specifications.

Since the products specified here are used in various operating conditions, their compatibility for the specific system must be based on specifications or after analysis and/or tests to meet your specific requirements. The expected performance and safety assurance will be the responsibility of the person who has determined the compatibility of the system. This person should continuously review the suitability of all items specified, referring to the latest catalogue information with a view to giving due consideration to any possibility of equipment failure when configuring a system.

2. Only trained personnel should operate pneumatically operated machinery and equipment.

Compressed air can be dangerous if an operator is unfamiliar with it. Assembly, handling or repair of pneumatic systems should be performed by trained and experienced operators.

- 3. Do not service machinery/equipment or attempt to remove components until safety is confirmed.
  - 1. Inspection and maintenance of machinery/equipment should only be performed after confirmation of safe locked-out control positions.
  - 2. When equipment is to be removed, confirm the safety process as mentioned above. Cut the supply pressure for this equipment and exhaust all residual compressed air in the system.
  - 3. Before machinery/equipment is restarted, take measures to prevent shooting-out of cylinder piston rod, etc. (Bleed air into the system gradually to create back pressure.)
- 4. Contact SMC if the product is to be used in any of the following conditions:
  - 1. Conditions and environments beyond the given specifications, or if product is used outdoors.
  - 2. Installation on equipment in conjunction with atomic energy, railway, air navigation, vehicles, medical equipment, food and beverages, recreation equipment, emergency stop circuits, press applications, or safety equipment.
  - 3. An application that has the possibility of having negative effects on people, property, or animals, and therefore requires special safety analysis.





Be sure to read before handling.

#### Design

# **⚠** Warning

#### 1. Actuator drive

When an actuator, such as a cylinder, is to be driven using a valve, take appropriate measures to prevent any potential danger caused by actuator operation.

#### 2. Intermediate stopping

When a 3-position closed centre valve is used to stop a cylinder's piston at an intermediate position, accurate stopping of the piston in a predetermined position is not possible due to the compressibility of air.

Furthermore, since valves and cylinders are not guaranteed for zero air leakage, it may not be possible to hold a stopped position for an extended length of time. Contact SMC if it is necessary to hold a stopped position for an extended time.

#### 3. Effect of back pressure when using a manifold

Use caution when valves are used on a manifold, as actuator malfunction due to back pressure may occur. Special caution is necessary when using a 3-position exhaust centre valve, or when driving a single acting cylinder. In cases where there is a danger of this kind of malfunction, take countermeasures by using a back-pressure check valve, an individual EXH spacer assembly, or an EXH blocking plate.

#### 4. Dealing with pilot exhaust

Operate the pilot exhaust port (PE) with silencers mounted on both the D and U sides, or with release to atmosphere. If merged with the main exhaust, the main valve may malfunction due to back pressure.

#### 5. Holding of pressure (including vacuum)

Since valves are subject to air leakage, they cannot be used for applications such as holding pressure (including vacuum) in a pressure vessel.

#### 6. Not for use as an emergency shutoff valve

None of the valves featured in this catalogue is designed for safety applications such as an emergency shutoff valve. If application to this type of system is required, other reliable safety assurance measures should also be adopted.

#### 7. Maintenance space

The installation should allow sufficient space for maintenance activities

#### 8. Release of residual pressure

Provide a residual pressure release function for maintenance purposes. Special consideration should be given to the release of residual pressure between the valve and cylinder in the case of a 3-position closed centre type valve.

#### 9. Vacuum applications

When a valve is used for vacuum switching, take appropriate measures against the suction of external dust or other contaminants through vacuum pads and exhaust ports. An external pilot type valve should be used in such cases. Contact SMC regarding the use of an internal pilot type or air operated valve.

# 10. Take suitable protective measures in locations or applications where valves are constantly exposed to water.

#### 11. Double solenoid applications

When a double solenoid type is used for the first time, the actuator may operate in an unexpected direction depending on the valve's switch position. Take appropriate measures to prevent potential danger caused by actuator operation.

#### 12. Ventilation

When using valves in a sealed control panel, install a vent to prevent rise of pressure inside the control panel caused by exhaust air and trapping of heat generated by the valve.

#### Selection

# **⚠** Warning

#### 1. Confirm all specifications.

The products featured in this catalogue are designed only for use in compressed air systems (including vacuum). Do not operate at pressures or temperatures beyond the range of specifications, as this can cause damage or malfunction. (Refer to specifica-tions.)

Contact SMC when using a fluid other than compressed air (including vacuum).

#### 2. Extended periods of continuous energization

- If a valve is continuously energized for an extended period, heat generation of the coil may result in a reduced performance and shorter service life of the valve or have an adverse effect on the peripheral equipment in proximity. For this reason, a low wattage type should be used when the energization is to continue for an extended period or the time in a day when the valve is energized is to be longer than the time when it is not. Under some operating conditions, valves other than the above can be used. For more information, please consult SMC. It is also possible to avoid the problem by shortening the energization time by using the valve as a N.O. (Normally open) type.
- When a valve is installed inside the control panel, take measures against heat radiation so that the temperature will stay within the prescribed temperature range for the valve. There will be a large increase in temperature especially when three or more adjacent manifold stations are continuously energized for an extended period or when A and B sides of a dual 3 port valve are both continuously energized for an extended period. Take special precautions in such cases.

# **⚠** Caution


#### 1. Momentary energization

If a double solenoid valve will be operated with momentary energization, it should be energized for at least 0.1 second.

However, depending on the secondary load conditions, it should be energized until the cylinder reaches the stroke end position. If the valve is to be used in an air blowing application, it should be energized continuously during the application.

#### 2. Leakage voltage

When using a C-R element (surge voltage suppressor) for protection of the switching element, please keep in mind that leakage voltage will increase due to leakage current flowing through the C-R element.



Limit the amount of residual leakage voltage to the following values:

With DC coil

2% or less of rated voltage





Be sure to read before handling.

#### Selection

# **△**Caution

#### 3. Surge voltage suppressor

If a general diode such as Zener diode or ZNR is used in the surge voltage suppressor on the controller side, be aware that there will be a residual voltage according to the protective element and rated voltage. The residual voltage of the diode is approximately 1V.

#### 4. Low temperature operation

Avoid ambient temperatures outside the range of  $-10^{\circ}$ C to  $50^{\circ}$ C. At low temperatures, take any necessary steps to avoid solidification or freezing of drainage and moisture.

#### 5. For air blowing applications

When using solenoid valves for air blowing, use external pilot type valves.

Also, air supply to the external pilot port should be compressed air that is within the pressure range prescribed in the specifications.

#### 6. Mounting orientation

In the case of a single solenoid, the mounting orientation is unrestricted. In the case of double solenoid or 3-position valves, mount so that the spool valve is horizontal.

Also, when mounting for an application that will inevitably involve vibration or impact, mount so that the spool valve is at a right angle to the direction of vibration.

Do not use in applications where vibration or impact exceed the product's specifications.

#### Mounting

# **△**Warning

# 1. If air leakage increases or equipment does not operate properly, stop operation.

After mounting, repairs, or equipment modification, connect the compressed air and power supplies, and perform appropriate function and leakage inspections to confirm that the unit is mounted properly.

#### 2. Instruction manual

Mount and operate the product only after reading the manual carefully and understanding its contents. Always keep the manual handy for easy reference.

#### 3. Painting and coating

Warnings or specifications printed or pasted on the product should not be erased, removed or covered up.

#### **Piping**

# **⚠** Caution

#### 1. Preparation before piping

Before piping is connected, it should be thoroughly flushed out with air or washed out with water to remove chips, cutting oil and other debris.

#### 2. Wrapping of sealant tape

When connecting pipes and fittings, etc., be sure that neither chips from the pipe threads nor sealing material get inside the valve.

When using sealant tape, leave 1.5 to 2 thread ridges exposed at the end of the pipe/fitting.



#### 3. When using closed center type valves

When using closed center type valves, check carefully to make sure there are no air leaks from the piping between the valves and cylinders.

# 4. Ensure tightening to the prescribed tightening torques.

When screwing fittings into valves, tighten according to the torques given below.

#### 1) For M3, M5 threads

1-1) When using SMC fittings, tighten in the following manner: After tightening by hand, tighten an additional 1/4 rotation for M3 and 1/6 rotation for M5 with a tool. When using a miniature fitting, however, tighten an additional 1/4 rotation with a tool after tightening by hand. When there are 2 gaskets, as in the case of a universal elbow or universal tee, tighten an additional 1/2 rotation.

Note) Over-tightening will cause breakage of the fitting threads or deformation of the gasket, resulting in air leakage. Under-tightening will cause loosening or air leakage.

1-2) When using fittings other than SMC products, follow the instructions by the respective manufacturers.

#### Tightening torques for piping

| Connection thread | Proper tightening torque (N·m) |  |
|-------------------|--------------------------------|--|
| Rc 1/8            | 7 to 9                         |  |
| Rc 1/4            | 12 to 14                       |  |
| Rc 3/8            | 22 to 24                       |  |
| Rc 1/2            | 28 to 30                       |  |
| Rc 3/4            | 28 to 30                       |  |

#### 5. Connection of piping to products

When connecting piping to a particular product, refer to the product's instruction manual to avoid mistakes regarding the supply port and other connections as applicable.





Be sure to read before handling.

#### Wiring

# **△** Caution

#### 1. Polarity

Always confirm whether or not there is polarity when connecting a power supply to a DC specification solenoid valve equipped with a (light) voltage surge suppressor.

If there is a polarity, observe the following precautions:

- If there is no built-in diode for polarity protection:
- Switching polarity by mistake poses the danger of burnout to the valve's built-in diode and the switching element on the control mechanism side, as well as to the power supply mechanism.
- If there is a diode for polarity protection:
- Switching polarity by mistake will cause the valve's switching function to stop.
- \* Series VQ4000 has no polarity. (It is a polarity-free type valve.)

#### 2. Applied voltage

Be careful to apply the proper voltage when connecting electric power to the solenoid valve. Application of improper voltage may cause malfunction or coil damage.

#### 3. Confirm the connections.

After completing the wiring, confirm that all the connections are correct

#### Lubrication

# **A** Caution

## 1. Lubrication

#### [Rubber seal]

- The valve has been lubricated for life at the factory, and does not require any further lubrication.
- Should you wish to apply additional lubrication, however, please be sure to use ISO VG32 Class 1 turbine oil (without additives).

Please be aware, however, that once additional lubrication is applied, it must be continued to avoid malfunctions, as the new lubricant will completely cancel out the original lubrication.

#### [Metal seal]

- The valve has been lubricated for life at the factory and does not require any further lubrication.
- Should you wish to apply additional lubrication, however, please be sure to use ISO VG32 Class 1 turbine oil (without additives).

#### **Air Supply**

# **Marning**

#### 1. Use clean air.

Do not use compressed air which contains chemicals, synthetic oils containing organic solvents, salts or corrosive gases, etc., as this can cause damage or malfunction.

## 

#### 1. Install air filters.

Install air filters close to valves at their upstream side. A filtration degree of  $5\mu m$  or less should be selected.

#### 2. Install an air dryer or after-cooler.

Compressed air that includes excessive drainage may cause malfunction of valves and other pneumatic equipment. To prevent this, install an air dryer or after-cooler.

3. If excessive carbon powder is generated, eliminate it by installing mist separators at the upstream side of valves.

If excessive carbon powder is generated by the compressor, it may adhere to the inside of valves and cause malfunction.

Refer to SMC's "Air Cleaning Equipment" catalogue for further details on compressed air quality.

#### **Operating Environment**

# **Marning**

- 1. Do not use valves where there is direct contact with, or in atmospheres of, corrosive gases, chemicals, salt water, water or steam.
- 2. Do not use in an explosive atmosphere.
- 3. Do not use in locations subject to vibration or impact. Confirm the specifications for each series.
- 4. A protective cover should be used to shield valves from direct sunlight.
- 5. Shield valves from radiated heat generated by nearby heat sources.
- 6. Employ suitable protective measures in locations where there is contact with water droplets, oil, or welding spatter.
- 7. When solenoid valves are mounted in a control panel or are energized for extended periods of time, employ measures to radiate excess heat so that temperatures remain within the valve specification range.
- 8. Products with IP65 enclosures (based on IEC529) are protected against dust and water, however, these products cannot be bathed in water.
- Products with enclosure conforming to IP65 rating will satisfy the specifications only if they are installed correctly. Therefore, be sure to read the instructions for respective products.





Be sure to read before handling.

#### **Maintenance**

# **Marning**

# 1. Perform maintenance procedures as shown in the instruction manual.

If handled improperly, malfunction or damage of machinery or equipment may occur.

# 2. Equipment removal and supply/exhaust of compressed air

When equipment is to be removed, first confirm that measures are in place to prevent dropping of driven objects and run-away of equipment, etc. Then cut the supply air pressure and electric power, and exhaust all compressed air from the system using its residual pressure release function.

When the equipment is to be started again after remounting or replacement, first confirm that measures are in place to prevent lurching of actuators and then confirm that equipment operates normally.

#### 3. Infrequent operation

Valves should be switched at least once every 30 days to prevent malfunction. (Use caution regarding the air supply.)

#### 4. Manual override operation

When the manual override is operated, connected equipment will be actuated. Confirm safety before operating.

# **⚠** Caution

#### 1. Filter drainage

Drain out condensate from air filters regularly. (Refer to specifications.)

#### 2. Lubrication

In the case of rubber seals, once lubrication has been started, it must be continued.

Use VG32 Class 1 turbine oil (without additives). Other lubricating oils will cause malfunctions.

Contact SMC regarding VG32 Class 2 turbine oil (with additives).



# $\triangle$

# Series VQC

# **Specific Product Precautions 1**

Be sure to read before handling. Refer to pages 63 through 67 for Safety instructions and common precautions.

# **Marning**


#### **Manual Override**

Since connected equipment will operate when the manual override is activated, confirm that conditions are safe prior to activation.

The non-locking push type (tool required) is standard, and the slotted locking type (tool required) is optional.

#### ■ VQC1000/2000

#### Non-locking push type (tool required)






Push down the manual override button with a small screwdriver, etc., until it stops.

The manual override will return when released.


#### Slotted locking type (tool required) <Optional>






Push down the manual override button with a small flat head screwdriver until it stops, and turn it clockwise 90° to lock it. Turn it counterclockwise to release it.

#### Locking type (manual) <Optional>




Push down the manual override button with a small flat head screwdriver or with your finger until it stops, and turn it clockwise 90° to lock it. Turn it counterclockwise to release it.

#### Slide locking type (manual) < Optional>




Slide the manual override button with a small flat head screwdriver or with your finger until it stops at the pilot valve side (ON side) to lock it. Slide it to the fitting side (OFF side) to release it. It can also be used as a push type using a screwdriver, etc., of Ø1.7 or less in case of VQC1000, Ø2 or less in case of VQC2000.




#### ■ VQC4000

#### Non-locking push type (tool required)




Locking type (manual) <Optional>



Push down the manual override button with a small screwdriver until it stops.


The manual override will return when released.

Push down the manual override button with a small flat head screwdriver until it stops, and turn it clockwise 90° to lock it. Turn it counterclockwise to release it.



## **⚠** Caution

#### Solenoid Valve Removal and Mounting VQC1000/2000



#### Removal steps

- Loosen the clamp screws until they turn freely. (The screws do not come out.)
- Remove the solenoid valve from clamp B by lifting the coil side of the valve while pushing on the screw top.

If pushing down on the screw is difficult, you can alternately press down on the valve gently in the area near the manual override.

#### **Mounting steps**

- **1.** Push the clamp screws. Clamp A opens. Now insert the end plate hook of the valve into clamp B from an angle.
- Push the valve down into place. (When you release the screws, the valve will be locked into clamp A.)
- 3. Tighten the clamp screws with a tightening torque of 0.25 to 0.35N·m for VQC1000 and 0.5 to 0.7N·m for VQC2000.

#### **⚠**Caution


Do not let foreign matter stick on the seal side of the gasket and solenoid, as this will cause air leakage.



**VQC4000** 

After confirming that the gasket is installed correctly, securely tighten the mounting screws according to the tightening torque shown below.

Mounting screw (M3)







# Series VQC Specific Product Precautions 2

Be sure to read before handling. Refer to pages 63 through 67 for Safety instructions and common precautions.

## **⚠** Caution

#### **Replacing One-touch fittings**


Cylinder port fittings are available in cassette type and can be replaced easily.

Fittings are secured with a retaining clip that is inserted from the top side of the valve. After removing the valve, remove the clip with a flat head screw driver to replace the fittings.

To mount a fitting, insert the fitting assembly until it stops and reinsert the retaining clip to its designated position.

# Fitting assembly Clip VQC1000 VQC1000 VQC2000

| Amuliantia tuta O.D. | Fitting assembly part no. |                |  |  |
|----------------------|---------------------------|----------------|--|--|
| Applicable tube O.D. | VQC1000                   | VQC2000        |  |  |
| ø3.2                 | VVQ1000-50A-C3            | _              |  |  |
| ø <b>4</b>           | VVQ1000-50A-C4            | VVQ1000-51A-C4 |  |  |
| ø <b>6</b>           | VVQ1000-50A-C6            | VVQ1000-51A-C6 |  |  |
| ø <b>8</b>           | _                         | VVQ1000-51A-C8 |  |  |
| M5                   | VVQ1000-50A-M5            | _              |  |  |
| ø1/8"                | VVQ1000-50A-N1            | _              |  |  |
| ø <b>5/32</b> "      | VVQ1000-50A-N3            | VVQ1000-51A-N3 |  |  |
| ø1/4"                | VVQ1000-50A-N7            | VVQ1000-51A-N7 |  |  |
| ø5/16"               | _                         | VVQ1000-51A-N9 |  |  |




| Applicable tube O.D. | Fitting assembly part no. |  |  |
|----------------------|---------------------------|--|--|
| Applicable tube O.D. | VQC4000                   |  |  |
| ø <b>8</b>           | VVQ4000-50B-C8            |  |  |
| ø10                  | VVQ4000-50B-C10           |  |  |
| ø12                  | VVQ4000-50B-C12           |  |  |
| ø1/4"                | VVQ4000-50B-N7            |  |  |
| ø5/16"               | VVQ4000-50B-N9            |  |  |
| ø <b>3/8</b> "       | VVQ4000-50B-N11           |  |  |

## **⚠** Caution


Light/Surge voltage suppressor VQC1000/2000

Indicator lights are all positioned on one side for both single solenoid and double solenoid type valves.

For double solenoid type, 2 colours that are same as the manual override are used to indicate the energization of A-side or B-side.




(For VQC1000)



# **⚠** Caution

## **Internal Wiring Specifications**

**VQC4000** 



#### How to Find the Flow Rate

Refer to pages 61 and 62.



# Series VQC Specific Product Precautions 3

Be sure to read before handling. Refer to pages 63 through 67 for Safety instructions and common precautions.

#### Serial Wiring EX500/EX250/EX240/EX126 Precautions

# **△Warning**

1. These products are intended for use in general factory automation equipment.

Avoid using these products in machinery/equipment which affects human safety, and in cases where malfunction or failure can result in extensive damage.

- 2. Do not use in explosive environments, in the presence of inflammable gases, or in corrosive environments. This can cause injury or fire.
- 3. Work such as transporting, installing, piping, wiring, operation, control and maintenance should be performed by knowledgable and qualified personnel only. As handling involves the risk of a danger of electrocution, injury or fire.
- 4. Install an external emergency stop circuit that can promptly stop operation and shut off the power supply.
- 5. Do not modify these products. Modifications done to these products carry the risk of injury and damage.

## **△**Caution

- 1. Read the instruction manual carefully, strictly observe the precautions and operate within the range of the specifications.
- 2. Do not drop these products or submit them to strong impacts. This can cause damage, failure or malfunction.
- 3. In locations with poor electrical conditions, take steps to ensure a steady flow of the rated power supply. Use of a voltage outside of the specifications can cause malfunction, damage to the unit, electrocution or fire.
- 4. Do not touch connector terminals or internal circuit elements when current is being supplied. There is a danger of malfunction, damage to the unit or electrocution if connector terminals or internal circuit elements are touched when current is being supplied.

Be sure that the power supply is OFF when adding or removing manifold valves or input blocks or when connecting or disconnecting connectors.

5. Operate at an ambient temperature that is within the specifications. Even when the ambient temperature range is within the specifications, do not use in locations where there are rapid temperature changes.

## **△** Caution

- 6. Keep wire scraps and other extraneous materials from getting inside these products. This can cause fire, failure or malfunction.
- 7. Give consideration to the operating environment depending on the type of enclosure being used.

To achieve IP65 and IP67 protection, provide appropriate wiring between all units using electrical wiring cables, communication connectors and cables with M12 connectors. Also, provide waterproof caps when there are unused ports, and perform proper mounting of input units, input blocks, SI units and manifold valves. Provide a cover or other protection for applications in which there is constant exposure to water.

8. Use the proper tightening torques.

There is a possibility of damaging threads if tightening exceeds the tightening torque range.

9. Adjustment and operation.

Use a sharp-ended watchmakers screw driver to set the dip switches and rotary switches.

- 10. Provide adequate protection when operating in locations such as the following:
  - Where noise is generated by static electricity
  - Where there is a strong electric field
  - Where there is a danger of exposure to radiation
  - When in close proximity to power supply lines
- 11. When these products are installed in equipment, provide adequate protection against noise by using noise filters.
- 12. Since these products are components whose end usage is obtained after installation in other equipment, the customer should confirm conformity to EMC directives for the finished product.
- 13. Do not remove the name plate.
- 14. Perform periodic inspections and confirm normal operation, otherwise it may be impossible to guarantee safety due to unexpected malfunction or erroneous operation.





# Series VQC Specific Product Precautions 4

Be sure to read before handling. Refer to pages 63 through 67 for Safety instructions and common precautions.

#### When one AS-i power supply system is used

## **⚠** Caution

|               |                                 | TCW  | SDTC | TDW         | SDTD  |
|---------------|---------------------------------|--|------|-------------|-------|
| Pow           | er supply voltage               | Supplied from AS-i circuit, 26.5 to 31.6 VDC Note 1) |      |             |       |
| Curre         | ent consumption Note 2)         | Max. 100 mA Max.65 mA                                |      |             | S5 mA |
| o et          | Number of inputs                | 8  |      | 4           |       |
| outp<br>icati | Number of outputs               | 8  |      | 4           |       |
| out/c         | Valve supply voltage            | 24 VDC ± 10%   |      |             |       |
| a spe         | Possible supply current Note 3) | Max. 240 mA  |      | Max. 120 mA |       |

Note 1) For communication power supply, use a power supply dedicated to AS-i. For details, please refer to instruction manuals provided by the respective manufacturers.

Note 2) Current consumption of SI unit internal power supply
Note 3) The AS-i circuit provides current to the internal parts of
the SI unit and all connected equipment.

Since there is a limit on the possible supply current to all connected equipment, select the equipment connected to the input block, such as sensors and valves, to stay within the possible supply current.

#### Example) When SDTD type is used

Valve: VQC1100NY - 5 (low wattage type of 0.5 W) × 4 pcs.

 $0.5 \text{ [W]} \div 24 \text{ [V]} \times 4 \text{ [pcs.]} = 84 \text{ [mA]} (4 \text{ outputs simultaneously ON)}$ 

The maximum possible supply current of SDTD is 120 mA. Therefore, the possible supply current to the sensor connected to the input block is

120 [mA] - 84 [mA] = 36 [mA].

Use of low wattage type valves by minimizing the maximum number of simultaneous outputs, and low current consumption sensors (2 wire sensor, etc.) connected to the input block is recommended.

#### **Power Supply Safety Instructions**

# **△** Caution

- Operation is possible with a single power supply or a separate power supply. However, be sure to provide two wiring systems (one for solenoid valves, and one for input and control units).
- 2. Use the following UL approved products for DC power supply combinations.
  - (1) Controlled voltage current circuit conforming to UL508 Circuit uses the secondary coil of an isolated transformer as the power supply, satisfying the following conditions.
    - Max. voltage (with no load): 30Vrms (42.4V peak) or less
    - Max. current: 1 8A or less (including shorts), and
      - When controlled by a circuit protector (fuse) with the following ratings:

| No-load voltage (V peak)       | Max. current rating |  |
|--------------------------------|---------------------|--|
| 0 to 20 [V]                    | 5.0                 |  |
| Over 20 [\/] and up to 20 [\/] | 100                 |  |
| Over 20 [V] and up to 30 [V]   | Peak voltage value  |  |

(2) A circuit (class 2 circuit) with maximum 30Vrms (42.4V peak) or less, and a power supply consisting of a class 2 power supply unit conforming to UL1310, or a class 2 transformer conforming to UL1585.

#### **Cable Safety Instructions**

# **⚠** Caution

- 1. Avoid miswiring, as this can cause malfunction, damage and fire in the unit.
- 2. Do not conduct wiring work while the cables are energized.
  - The SI unit may be damaged or malfunction.
- 3. To prevent noise and surge in signal lines, keep all wiring separate from power lines and high voltage lines. Otherwise, this can cause a malfunction.
- 4. Check wiring insulation, as defective insulation can cause damage to the unit when excessive voltage or current is applied.
- Do not bend or pull cables repeatedly, and do not place heavy objects on them or allow them to be pinched. This can cause broken lines.









#### **EUROPEAN SUBSIDIARIES:**



#### Austria

SMC Pneumatik GmbH (Austria). Girakstrasse 8, A-2100 Korneuburg Phone: +43 2262-62280, Fax: +43 2262-62285 E-mail: office@smc.at http://www.smc.at



#### Belgium

SMC Pneumatics N.V./S.A Nijverheidsstraat 20, B-2160 Wommelgem Phone: 03-355-1464, Fax: 03-355-1466 E-mail: post@smcpneumatics.be



#### Bulgaria

SMC Industrial Automation Bulgaria o.o.d. Vitinia str., bl. 89, entr. V app. 41, BG-1517 Sofia Phone:+359 2 9744492, Fax:+359 2 9744519 E-mail: sales@smc.at http://www.smc.ba



Czech Republic
SMC Industrial Automation CZ s.r.o. Hudcova 78a, CZ-61200 Brno Phone: +420 5 414 24611, Fax: +420 5 412 18034 E-mail: office@smc.cz http://www.smc.cz



#### Denmark

SMC Pneumatik A/S Knudsminde 4B, DK-8300 Odder Phone: (45)70252900, Fax: (45)70252901 E-mail: smc@smc-pneumatik.dk



#### Estonia

SMC Pneumatics Estonia OÜ Laki 12-101, 106 21 Tallinn Phone: 06 593540, Fax: 06 593541 http://www.smcpneumatics.ee



#### Finland

SMC Pneumatics Finland OY PL72, Tiistinniityntie 4, SF-02031 ESPOO Phone: 09-859 580. Fax: 09-8595 8595 http://www.smcfitec.sci.fi



SMC Pneumatique, S.A. 1, Boulevard de Strasbourg, Parc Gustave Eiffel Bussy Saint Georges F-77607 Marne La Vallee Cedex 3 Phone: 01-6476 1000, Fax: 01-6476 1010 http://www.smc-france.fr



#### Germany

SMC Pneumatik GmbH Boschring 13-15, D-63329 Egelsbach Phone: 06103-4020, Fax: 06103-402139 E-mail: info@smc-pneumatik.de http://www.smc-pneumatik.de



#### Greece

S. Parianopoulus S.A. Konstantinoupoleos Street, GR-11855 Athens Phone: 01-3426076, Fax: 01-3455578



#### Hungary

SMC Hungary Ipari Automatizálási Kft. Budafoki ut 107-113, H-1117 Budapest Phone: +36 1 371 1343, Fax: +36 1 371 1344 E-mail: office@smc-automation.hu http://www.smc-automation.hu



#### Ireland

SMC Pneumatics (Ireland) Ltd. 2002 Citywest Business Campus, Naas Road, Saggart, Co. Dublin Phone: 01-403 9000, Fax: 01-464-0500



#### Italy

SMC Italia S.p.A Via Garibaldi 62, I-20061Carugate, (Milano) Phone: 02-92711, Fax: 02-9271365 E-mail: mailbox@smcitalia.it http://www.smcitalia.it



#### Latvia

SMC Pneumatics Latvia SIA Smerla 1-705, Riga LV-1006, Latvia Phone: 0777-94-74, Fax: 0777-94-75 http://www.smclv.lv



#### Lithuania

UAB Ottensten Lietuva Savanoriu pr. 180, LT-2600 Vilnius, Lithuania Phone/Fax: 370-2651602



#### Netherlands

SMC Pneumatics BV De Ruyterkade 120, NL-1011 AB Amsterdam Phone: 020-5318888, Fax: 020-5318880 E-mail: info@smcpneumatics.nl



#### Norway

SMC Pneumatics Norway A/S Vollsveien 13 C, Granfos Næringspark N-1366 Lysaker Tel: (47) 67 12 90 20, Fax: (47) 67 12 90 21 http://www.smc-norge.no



#### Poland

SMC Industrial Automation Polska Sp.z.o.o. ul. Konstruktorska 11A, PL-02-673 Warszawa, Phone: +48 22 548 5085, Fax: +48 22 548 5087 E-mail: office@smc.pl http://www.smc.pl



#### Portugal

SMC Sucursal Portugal, S.A. Rua de Eng<sup>o</sup> Ferreira Dias 452, 4100-246 Porto Phone: 22-610-89-22, Fax: 22-610-89-36 E-mail: postpt@smc.smces.es



#### Romania

SMC Romania srl Str Frunzei 29, Sector 2, Bucharest Phone: 01-324-2626, Fax: 01-324-2627 E-mail: smccadm@canad.ro http://www.smcromania.ro



#### Russia

Russia SMC Pneumatik LLC. 36/40 Sredny pr. St. Petersburg 199004 Phone.:(812) 118 5445, Fax:(812) 118 5449 E-mail: smcfa@peterlink.ru http://www.smc-pneumatik.ru



#### Slovakia

SMC Priemyselná Automatizáciá, s.r.o. Námestie Martina Benku 10 SK-81107 Bratislava Phone: +421 2 444 56725. Fax: +421 2 444 56028 E-mail: office@smc.sk http://www.smc.sk



#### Slovenia

SMC industrijska Avtomatika d.o.o. Grajski trg 15, SLO-8360 Zuzemberk Phone: +386 738 85240 Fax: +386 738 85249 E-mail: office@smc-ind-avtom.si http://www.smc-ind-avtom.si



Spain SMC España, S.A. Zuazobidea 14 01015 Vitoria Phone: 945-184 100, Fax: 945-184 124 E-mail: post@smc.smces.es



#### Sweden

SMC Pneumatics Sweden AB Ekhagsvägen 29-31, S-141 71 Huddinge Phone: 08-603 07 00, Fax: 08-603 07 10 http://www.smc.nu



#### Switzerland

SMC Pneumatik AG Dorfstrasse 7, CH-8484 Weisslingen Phone: 052-396-3131, Fax: 052-396-3191 E-mail: info@smc.ch http://www.smc.ch



#### Turkey

Entek Pnömatik San. ve Tic Ltd. Sti. Perpa Tic. Merkezi Kat: 11 No: 1625, TR-80270 Okmeydani Istanbul Phone: 0212-221-1512, Fax: 0212-221-1519 http://www.entek.com.tr



SMC Pneumatics (UK) Ltd Vincent Avenue, Crownhill, Milton Keynes, MK8 0AN Phone: 0800 1382930 Fax: 01908-555064 E-mail: sales@smcpneumatics.co.uk http://www.smcpneumatics.co.uk



#### OTHER SUBSIDIARIES WORLDWIDE:

ARGENTINA, AUSTRALIA, BOLIVIA, BRASIL, CANADA, CHILE, CHINA, HONG KONG, INDIA, MALAYSIA, MEXICO, NEW ZEALAND, PHILIPPINES, SINGAPORE, SOUTH KOREA, TAIWAN, THAILAND, USA, VENEZUELA

> http://www.smceu.com http://www.smcworld.com